

Über dieses Buch

Dies ist ein digitales Exemplar eines Buches, das seit Generationen in den Regalen der Bibliotheken aufbewahrt wurde, bevor es von Google im Rahmen eines Projekts, mit dem die Bücher dieser Welt online verfügbar gemacht werden sollen, sorgfältig gescannt wurde.

Das Buch hat das Urheberrecht überdauert und kann nun öffentlich zugänglich gemacht werden. Ein öffentlich zugängliches Buch ist ein Buch, das niemals Urheberrechten unterlag oder bei dem die Schutzfrist des Urheberrechts abgelaufen ist. Ob ein Buch öffentlich zugänglich ist, kann von Land zu Land unterschiedlich sein. Öffentlich zugängliche Bücher sind unser Tor zur Vergangenheit und stellen ein geschichtliches, kulturelles und wissenschaftliches Vermögen dar, das häufig nur schwierig zu entdecken ist.

Gebrauchsspuren, Anmerkungen und andere Randbemerkungen, die im Originalband enthalten sind, finden sich auch in dieser Datei – eine Erinnerung an die lange Reise, die das Buch vom Verleger zu einer Bibliothek und weiter zu Ihnen hinter sich gebracht hat.

Nutzungsrichtlinien

Google ist stolz, mit Bibliotheken in partnerschaftlicher Zusammenarbeit öffentlich zugängliches Material zu digitalisieren und einer breiten Masse zugänglich zu machen. Öffentlich zugängliche Bücher gehören der Öffentlichkeit, und wir sind nur ihre Hüter. Nichtsdestotrotz ist diese Arbeit kostspielig. Um diese Ressource weiterhin zur Verfügung stellen zu können, haben wir Schritte unternommen, um den Missbrauch durch kommerzielle Parteien zu verhindern. Dazu gehören technische Einschränkungen für automatisierte Abfragen.

Wir bitten Sie um Einhaltung folgender Richtlinien:

- + *Nutzung der Dateien zu nichtkommerziellen Zwecken* Wir haben Google Buchsuche für Endanwender konzipiert und möchten, dass Sie diese Dateien nur für persönliche, nichtkommerzielle Zwecke verwenden.
- + *Keine automatisierten Abfragen* Senden Sie keine automatisierten Abfragen irgendwelcher Art an das Google-System. Wenn Sie Recherchen über maschinelle Übersetzung, optische Zeichenerkennung oder andere Bereiche durchführen, in denen der Zugang zu Text in großen Mengen nützlich ist, wenden Sie sich bitte an uns. Wir fördern die Nutzung des öffentlich zugänglichen Materials für diese Zwecke und können Ihnen unter Umständen helfen.
- + Beibehaltung von Google-Markenelementen Das "Wasserzeichen" von Google, das Sie in jeder Datei finden, ist wichtig zur Information über dieses Projekt und hilft den Anwendern weiteres Material über Google Buchsuche zu finden. Bitte entfernen Sie das Wasserzeichen nicht.
- + Bewegen Sie sich innerhalb der Legalität Unabhängig von Ihrem Verwendungszweck müssen Sie sich Ihrer Verantwortung bewusst sein, sicherzustellen, dass Ihre Nutzung legal ist. Gehen Sie nicht davon aus, dass ein Buch, das nach unserem Dafürhalten für Nutzer in den USA öffentlich zugänglich ist, auch für Nutzer in anderen Ländern öffentlich zugänglich ist. Ob ein Buch noch dem Urheberrecht unterliegt, ist von Land zu Land verschieden. Wir können keine Beratung leisten, ob eine bestimmte Nutzung eines bestimmten Buches gesetzlich zulässig ist. Gehen Sie nicht davon aus, dass das Erscheinen eines Buchs in Google Buchsuche bedeutet, dass es in jeder Form und überall auf der Welt verwendet werden kann. Eine Urheberrechtsverletzung kann schwerwiegende Folgen haben.

Über Google Buchsuche


Das Ziel von Google besteht darin, die weltweiten Informationen zu organisieren und allgemein nutzbar und zugänglich zu machen. Google Buchsuche hilft Lesern dabei, die Bücher dieser Welt zu entdecken, und unterstützt Autoren und Verleger dabei, neue Zielgruppen zu erreichen. Den gesamten Buchtext können Sie im Internet unter http://books.google.com/durchsuchen.


This is a reproduction of a library book that was digitized by Google as part of an ongoing effort to preserve the information in books and make it universally accessible.



https://books.google.com







Fly Fisher's Guide,

ILLUSTRATED BY

COLOURED PLATES, 1040 des5

REPRESENTING

UPWARDS OF FORTY OF THE MOST USEFUL

FLIES。

Accurately Copied from Mature.

1

GEO. C. BAINBRIDGE

And lightly on the dimpling eddy fling The hypocritic fly's unruffled wing.

THE ANGLERS, DIA. 3.

Aiberpool:

PRINTED FOR THE AUTHOR

BY G. F. HARRIS'S WIDOW AND BROTHERS;


And Sold by Longman, Hurst, Rees, Orme, and Brown, London; and Wright and Cruickshank, Liverpool.

1816.



The state of the s

ing the equation of the control of t



PLATE

Google

..,Coogle

PREFACE.

Custom having pronounced that a book is incomplete without a prefatory introduction, it might savour of arrogance if the tribute were witheld in the present instance, although to a novice the task of complying with this injunction is not a little embarrassing.

In order to explain the motives which directed the intrusion of the following pages upon the public, it may be necessary to premise that desire of fame, or expectation of profit, was not amongst the number. A wish that every lover of the Angle should participate in the advantages to be derived from

a constant reference to the representations of the Insects, on which his diversion so materially depends; and, the hope that from this humble attempt the idea of a complete work on Water Insects would suggest itself to some person more capable of the undertaking, induced the writer to publish his Observations on Angling, and Specimens of Flies, which were originally only intended for private inspection.

The insignificant light in which publications of this nature are generally held by the Literati, and the indifference with which they are so often treated by those who have no inclination for rural sports, may probably screen this treatise from the lash of the critic. And as it is the wish of the Author that it should be disseminated amongst FRIENDS only, (for as such he has been accustomed to consider every brother of the Angle) he throws himself upon their good nature for lenity in criticism where they disapprove, and for candour in approbation should any portion of the matter be in unison with their own ideas, or contribute in any wise to their success. Relying upon which, he has the honour to subscribe himself

Their most obedient humble servant,

G. C. B.

LIVERPOOL, 1st MARCH, 1816.

Table of Contents.


	Page
Of the advantages of Fly Fishing	1
Of the Materials used in Fly Fishing	
Of the Rod · · · · · · · · · · · · · · · · · · ·	13
Of Lines · · · · · · · · · · · · · · · · · · ·	21
Of Hooks ·····	28
Of Gut and Weed	33
Of the Reel ·····	36
Of the Pannier · · · · · · · · · · · · · · · · · · ·	39
Of Pocket Books · · · · · · · · · · · · · · · · · · ·	40
Description of the mode of Tying Flies	42
Rules to be observed in Angling	51
Proper Seasons and Times for Angling	60
Of the Salmon	64
Of the Trout	76
Of the Gravel Fry	80
Of the Grayling, or Umber	82
Of the Gruining	85
Of the Gray Mullet	87
Of the Chub, Chevin, or Chavinder	89
Of the Bleak	90

viii

Of t	he Roach.	and the Do	ice Dare or	· Showler •	• • • • • • • • •	Page 91
•	-	Salmon Fla				
		- Trout Flie	-			
		- Ditto,	•		• • • • • • • • •	
		- Ditto,	in plate	6		119
		- Ditto,				
		- Ditto,	in plate	8		
Of ti	he Moths,	for Night 1	Fishing · ·	• • • • • • • • • •	•••••	142
		serving Gent				
of C	Figure 1	shing with a	Running	Line · · · ·		145
of T	rolling,	or Minnow 1	Fishing ••			147
		• • • • • • •	•••	• • • • • • •		to a factor
i 2	••••		•	. • . •		
	• • • • • •	• • •	• • • • • • • •	• • • • • • • • • • • • • • • • • • • •		
' í'.	• • • • • • •		• • • • • • • • •	• • • • • • • •	· · · ·	. •
З.,	••••		• • • • • • • •	• • • • • • • •	• • • • • • • • • • • • • • • • • • • •	
42.7		• • • • • • •	• • • • • • • • •	• • • • • • • • • • • • • • • • • • • •		
H.			• • • • • •			
<u>(.)</u>	•••••		*** 4			
16	• • • • •		• • • • • • •	•	•	
f			· · • • · · · · · · · · · · · · · · · ·			
* * *			• . • • • • • •	• •	•	- 4
: 7			• • • • • • •			
. 3	• • • • • • •	• • • • • • •	• • • • • • •			
1 44	• • • • •	*** ***		•	•	
2 "			•			

Coogle

ſ



Digitized by Google

FLY FISHING

AND ITS ADVANTAGES.



F the superiority which this particular branch of Angling possesses over every other method, so many

persons have written at length, and its merits have been so generally acknowledged by all who have had the opportunities of discriminating, that to enter diffusively into the particular advantages which distinguish it would be superfluous, and by no means in conformity with the intentions of the compiler.

It may, however, be necessary to point out a few of the leading characteristics which combine to render this delightful recreation so pre-eminent amongst Rural Sports; and in the course of the work to connect a few observations, in order to confute the objections which prejudiced persons are but too apt to bring forward in opposition to the gratifying pleasures which admirers of this pursuit so justly exhibit in a warm tone of colouring.

Without referring to the antiquity of the art, as a recommendation, or enumerating the catalogue of virtuous qualities, such as patience, perseverance, &c., of which an Angler is supposed to be possessed, it is simply necessary to observe, that many very eminent and learned characters have devoted much of their leisure time to this agreeable recreation; and it is a fact worthy of notice, that although many persons

have quitted other sports for the amusement of *Fly Fishing*, yet the memory of the writer does not furnish a single instance of a Fly Fisher deserting his occupation, and transferring his preference to any other of the list of Rural Sports: this observation is very general, and is certainly a strong argument in favour of the superior pleasure which Angling affords.

The peculiar and almost immediate relief which this innocent pursuit yields to the distressed or uneasy mind, by calming the perturbations which misfortunes or other vexatious circumstances may have excited, is to be ranked amongst the first of its recommendations. But as this relief is also experienced in some degree by the practiser of other modes of Angling, it may not be considered precisely correct to class it amongst the advantages of Fly Fishing. To proceed therefore to those observations, upon which the claim of

superiority is founded. The first which presents itself is exercise. The Fly Fisher is in constant motion, and travels several miles whilst practising his art: whereas the ground Angler remains in a state of inactivity, on the banks of some unwholesome pool; exposed to the damp air, and liable, from the want of exertion, to the attacks of ague and rheumatism, either of which will disable him for a considerable time, if not altogether, from pursuing his favourite occupation.

The beautiful and varied SCENERY which at each turn of the river is presented to the eye of the Fly Fisher is an inducement sufficiently attractive to make converts of the most sceptical, if they be not wholly indifferent to the beauties of nature. The course of a river being generally through the most romantic part of a country, the variety which occurs in following the stream for

a few miles, aided by the diversion which the rod affords, cannot fail to gratify the admirer of fine scenery in the highest degree. The dull monotony which attends the ground Angler, should his mind not be constantly engaged by the avidity of the finny tribe, is here avoided: whilst the Fly Fisher will frequently return home, gratified with the delights which his walk has afforded; even though he may not have been so successful in storing his pannier as he had anticipated.

The pleasure which the Angler derives from collecting and arranging the various materials necessary for the formation of the artificial Fly, and from the endeavour to approach the form and colours of nature, by the aid of these materials, is infinitely greater than can be conceived by an indifferent observer, and offers a constant employment for those leisure hours, which in

unfavourable weather might otherwise hang heavy, and by not being agreeably occupied lead to the introduction of that most disagreeable companion—ENNUI.

CHEAPNESS has been always urged in favour of Angling; and certain it is, that no other amusement can be procured at such an easy rate; for it is within the reach of the humblest individual.

In addition to the foregoing advantages, that of CLEANLINESS must not be omitted. How greatly preferable is the simple formation of an artificial fly of feathers and fur, to the unpleasantness attendant upon baiting a hook with worm, maggot or paste. The one will last during the diversion of a whole day, and with care much longer; whilst the other requires adjusting or renewing, after every trifling nibble; to say nothing of the cruelty which attaches to the intro-

duction of a hook into the worm whilst living, or the extraction of a gorged hook from the entrails of a ravenous fish.

Such indeed are the pleasures and advantages derived from this mode of Angling, that some of our best modern poets have considered its praises as worthy their talents and attention. Vide THOMSON, GAY, ARMSTRONG, WALLER, &c.

THE MATERIALS

USED IN

FLY FISHING.

Having set forth a few of the prominent recommendations of the art, it remains to conduct the reader, if an admirer of the pursuit, to the practical system; which having been founded upon the experience and observation of several years, may not be altogether uninstructive or uninteresting. The articles necessary for the Fly Fisher to be furnished with consist of RODS, LINES, REELS OF WINCHES, SILK-WORM GUT, HOOKS; a variety of FEATHERS of every hue, from the most gaudy to the most dusky tinge; SILKS of various shades; HACKLES from the neck and back of the domestic cock or hen; wings of many birds, but most particularly of the Bittern, Grouse, Woodcock, Partridge, Snipe, Landrail, Golden Plover, and Starling. Furs of every colour: amongst the most useful of which will be found the skins of Squirrels, Moles, Water-rats, Hare's ears, and fur from the neck of the same animal: Bear's hair, and Hog's down, (which will take a dye of any shade.) The light yellow fur from the neck of the Martin is also very valuable, but not easily to be obtained in the northern counties.

CAMLETS and MOHAIR of every hue, the latter being serviceable in almost all flies, inasmuch as it prevents the camlet or fur, with which it is commonly mixed, from imbibing so great a degree of moisture as it would otherwise do; by which means, also, the fly becomes more durable; and the glossy shining qualities, which mohair retains even in the water, will in many instances approach nearer to the appearance of the natural fly than any other substitute.

The hackles most in estimation are the duns light and dark; both of which, but particularly the former, are difficult to be met with perfectly free from grizzle. The red with black stripe down the middle is by no means common: next to these, in point of utility, is the red with black root, which is generally substituted when the former cannot be procured. Black hackles are of

late become more common than formerly, by the introduction of a breed of Spanish fowls, which are perfectly black, except the topping of the head. The proper time of the year for the selection and plucking of hackles is about Christmas; as the feathers are then perfect and free from that disagreeable matter, which at other times is generally found in the pen part of the feather. Should the Angler be so fortunate as to meet with a real dun bird, either cock or hen, he ought to secure it at any price, as he may be considered as possessing a treasure; for the same fowl will furnish him with grizzled hackles about May, and dun hackles at Christmas. thers from young birds before they have moulted are entirely useless, being too soft to play properly in the water. mottled bright feather from the back of a well grown Grouse, and the Wren's tail, are on no account to be neglected.

Of SILKS it will be necessary to have three degrees of strength, and as many varieties of shade as the fly dresser may deem necessary for his purpose. The first, which is commonly denominated strong barber's silk, must be used double, for spliceing the tops of rods. The second of a finer quality, for fastening the rings to the rod, and other casualties. The third, for whipping hooks and dressing flies, should be the finest netting silk: it is difficult to meet with the latter of a sufficiently delicate texture in any towns far distant from the metropolis. Mr. Clark, of the Golden Leg, Southampton-street, furnishes every shade and colour which can possibly be required, at a reasonable rate.

OSTRICH and PEACOCK harls are also indispensable requisites: the former of every possible colour is useful in flies for Salmon fishing; and the latter is very frequently

used for Trout flies also, as in the Marlow buzz, Orl fly, &c.

In addition to the foregoing, the following articles are necessary for the completion of the Angler's apparatus. A Landing Net, having a ferrule at the lower end, in which a gaff or hook necessary for landing a large fish may be fastened at pleasure: the net should be from eighteen inches to two feet in diameter, and fixed either to an ash, briar, or light iron hoop. If the banks of the river be steep, this article is very useful; but when gravel patches, or shelving shores are frequent, it is seldom called into action. The gaff or hook may be carried in the pocket with safety, and the point preserved by means of a cork.

A pair of small neat PLIARS is of great assistance in dressing flies, and a pair of fine pointed scissars absolutely necessary;

NEEDLES for picking out the dubbing; WAX for the silk; and a PANNIER with a broad leather strap to fasten on the shoulder, so that the fish may be carried with safety, and free from injury, close the list of necessaries; and as a few hints respecting the selection of the various articles may not be altogether unacceptable, they will be severally mentioned in regular order.

The ROD first claims notice as occupying the foremost place in the catalogue of implements; in the choice of which every care and attention must be exercised. Rods are made up in various manners, and of divers lengths and weights. Some prefer them of two pieces only, which are spliced together about the middle. These certainly throw a fly in a neater manner than those encumbered with ferrules can possibly do; as the spring from the hand is uninterrupted, consequently more regular; and they are

admirably adapted for the use of an Angler whose residence is near the scene of his diversion; but the awkwardness of length renders them troublesome and unwieldy companions, when a walk of some miles intervenes between the river and the Angler's dwelling. This description of rod is in general use in the northern counties of England, where ferrules are considered very objectionable.

The length and weight of the rod depend so much upon the fancy of the purchaser, that no positive rules can be laid down to guide him in these respects. The common length of a Trout rod is from twelve to fourteen feet; some persons prefer them even longer; but for the generality of streams the latter is quite sufficient, and for small rivers and brooks the former is much the most convenient and useful size.

For Salmon fishing a greater length, extending to seventeen or eighteen feet, and of proportionate strength, will enable the lover of this superior diversion to throw a greater extent of strong tackle than the common rods will admit of his doing.

The chief consideration in the choice of a rod, for whatever purpose it may be intended, is, that it be free from knots or cracks, and that it be regularly taper and pliant from the butt to the point; for if the spring be not regular from one extremity to the other, the check which the defective part causes will severely strain, if it do not actually break the piece. By the term pliant, it is not meant that the rod should be as limber and flexible as a cart whip, which extreme ought as carefully to be guarded against as too great stubbornness; but that it should play easily, and that the bend be slightly perceptible even in the bottom or

butt end. In this, however, as well as in the number of joints of which he may wish the rod to consist, the Angler will best consult his own judgment and inclination, which can hardly fail to be satisfied at some of the tackle shops in the metropolis; where an endless variety of every description, which imagination or caprice may require, will be offered to his inspection.

The best rods which the writer has hitherto met with are manufactured and sold by Henry Swann, of Langholm, North Britain. They consist of five pieces, and have screw joints at each ferrule, which is particularly desirable, as they always set true; and should the weather or accident wet them, the difficulty of separating the joints, which in common rods such a circumstance causes to swell considerably, is avoided.

An improvement may nevertheless be

pointed out in these rods; viz. to have the top joint spliced to the fourth piece, without any ferrule. A rod of this description with two spare tops, which originally cost only eighteen shillings, is, after the constant use of nearly nine years, in every respect as good as new, having in that interval been merely varnished twice.

To those persons who reside at a distance from the metropolis, or have no mechanic at hand to repair the accidents which may from time to time happen to these implements, a description of the materials and manner of forming a rod may be useful; indeed, a true Angler ought to be able, if not to manufacture, at least to repair his own rods, lines, reels, &c. as he will otherwise be frequently exposed to great inconvenience from the numerous and unforeseen accidents to which the practiser of this diversion is constantly liable.

The best rods are made from ash, hickory, and lancewood; ash for the bottom piece, hickory for the middle, and lancewood for the top joints: real bamboo is preferable to lancewood, if it can be procured of good quality, which is extremely difficult: logwood is sometimes used for the tops, and answers extremely well for Salmon or trolling rods; but this wood is not frequently to be met with of straight grain in pieces of sufficient length for rods; but if it should be, it is not equal in elasticity to well seasoned lancewood. Rose wood, and a wood from the Brazils, called partridge wood, may also be made use of for top pieces; but yew and briars do not answer the purpose, although frequently recommended by experimenters.

Before wood of any description is cut into lengths it should be perfectly seasoned; and whatever number of pieces the rod is to be composed of between the butt and top piece

they must all be cut from the same log; and not as is too frequently done, the second part from one piece of wood, the third from another, and so on; which not having undergone, the same degrees of seasoning, will never play regularly in the hand.

The first proceeding towards the formation of a rod is to plane each length into a four square; afterwards, by means of a taper wooden sett, into an octagon. They are then to be rounded with a common smoothing-plane, and finished with different sized hollow planes. The ferrules are to be fitted on whilst the joints are in the octagon form.

In the formation of a SPLICE both pieces should be fixed firmly parallel; by which means, if they be drawn steadily over the plane together, the joint must prove true; they are then to be slightly rubbed with wax or glue, and neatly fastened with silk, and

the waxed parts rubbed with a smooth chisel, previously to being varnished.

The RINGS must be placed in a regular line, and ought to diminish in size as gradually as the rod tapers: they are easily made by twisting a piece of soft brass wire round a tobacco pipe, and fastened together with hard solder.

The extreme end of the top piece is commonly of WHALEBONE; and the error of putting too great a length of this material is but too frequent. A very short piece, say of the length of four or five inches, is sufficient; this is generally finished up with a file, any sharp instrument being liable to take it off in irregular flakes.

In this state it only remains to varnish the rod, which is best effected by copal varnish, or Indian rubber dissolved over a slow fire in linseed oil. If a stain be required, nitric acid, or oil of vitriol will produce a brown colour, the acid being diluted according to the shade required.

To preserve rods after use, let them be well rubbed with salad oil or tallow, and kept in a moderately dry place until the return of the Angling season; when, after being carefully wiped, they will be found in excellent order. If the bottom piece be bored for the purpose of receiving a spare top, the inside should be oiled by means of a piece of rag fastened to the end of a stick.

OF LINES.

The LINES for Reels are to be purchased of every length from fifteen to one hundred and twenty yards, or even longer, at the tackle shops throughout the kingdom, and at a much cheaper rate than a private individual can manufacture them, if his time and trouble are to be considered of any value. But as motives of curiosity may induce some of the readers of this treatise to try their skill in this art, an explanation of the necessary process will be here attempted.

These lines are most generally composed of a mixture of silk and hair, and as before observed, are spun of various lengths. For common Trout fishing in rivers, twenty to twenty five yards are sufficient; for lakes where the fish are large, and a boat is not used, forty to fifty yards may be required; and for Salmon in large rivers, eighty or even a hundred will not be too great a quantity.

Single handed rod fishers prefer their reel lines to run taper to the point, so that they may, by merely fixing their foot length of gut to the line, wind it up close to their hand; and where the stream is narrow and bushes frequent, this is certainly a good plan. But, for bold streams, the reel line should be of equal thickness throughout, and not too fine, in order that a taper hair line of ten yards in length may be attached thereto.

The most important consideration in the making of lines is the selection of the hair, which must be round, even, and free from scales. If plucked from the tail of a young horse or mare, it is not so good as that which is to be procured from a four or five year old gelding; but the best is to be had from the tail of a well grown stallion, and those hairs are generally most free from blemish which grow from the middle of the tail. Black, although the strongest, is the least serviceable colour; brown, gray, and white,

are to be preferred, and ought to be picked with care, and assorted according to their different degrees of length and thickness.

For common foot lines an engine is not necessary, as they are easily made by separating the hairs with the fore finger and thumb of the left hand, (having first fastened them by a knot) and twisting them with the right, occasionally drawing the hand downwards to prevent the untwisted hairs from entang-Taper lines of any length or thickling. from two hairs upwards, may be thus put together, fastening each length of hair to its companion by a water knot, the ends of which should be cut close, and secured by a little waxed silk. When a very strong line is required, it may be adviseable to make use of the twisting-engine, which will enable the practitioner to complete his purpose more readily and effectually than with the fingers only.

The twisting engine which has been here mentioned is used in making reel lines free from knots, and may be had at almost all the tackle shops; or may be easily made by any ingenious watch-maker or white-smith with very slight directions. It is a small brass box containing four wheels, three of which are of small dimensions; the other is of larger size, and has a handle. The axis of each of these wheels is protruded from the plates of the box on both sides, and is hollow. This instrument may be screwed into the back of a chair or other substance, in such a manner, that the operator may employ his hands both before and behind the engine, which bears a reduced resemblance to the wheels used by rope-makers. It is necessary then to procure three balls of barber's yellow silk, somewhat longer than the line is intended to be made; and before fastening them to the respective tubes, due notice must be taken that the silk is so placed,

as to prevent its being untwisted by the action of the instrument; for should one of the threads be improperly placed, it will require an encreased degree of labour, and a neat line can never be produced.

The hairs, in proportion to the thickness of the line required, must next be introduced by means of small quills into the tubes, and twisted (perhaps two or more) with each end of the silk; when these lengths are twisted in, the quills must be taken out, and the tubes again fed with hair; and so on, until the whole of the silk be unwound from the balls. It is necessary to observe that the hairs should be of unequal length when introduced; otherwise, should it, after the commencement, be necessary to put in two hairs at one time, the line will be clumsy and uneven.

By immersing the hair for about ten

minutes in water, before using, it will spin much better than if used quite dry. The mode of chusing it, by trying or pulling, cannot be too much censured; as the hair will beyond a doubt resume its original form, and thereby raise knots which will render the line irregular, and liable to be easily broken.

Besides the engine before described, there is another of a simpler form, which answers very well for short lengths when a knot is used, and is much more easily managed, as it merely requires the silk or hair to be fastened to the iron hooks in front, and then twisted together. The same recipes will answer for staining hair which are used for silk-worm gut; but natural colours always claim the preference, and care must be taken not to allow oil to approach the hair, as it infallibly causes it to rot.

OF HOOKS.

Hooks are manufactured of different forms, and are usually distinguished by the names of

The Limerick, The Sneckbend, The Kendal, The Kirby.

Of these varieties a representation has been attempted. Vide PLATE 11. fig. 1, 2, 3, 4.

Although generally considered of minor importance by a number of Anglers, who are satisfied if they procure the size they want, no part of their apparatus requires more minute attention than these small implements, on which success certainly, in a great measure, depends. It is necessary to have the hooks perfectly tempered; that is, of such a degree of firmness, that they will

not bend, and yet not so hard as to snap readily. The best method of ascertaining whether or not the hooks be *properly* tempered, is to try them in a piece of cork; or for the points only, the thumb nail is sufficient.

Most writers on the subject of Angling mention a small whetstone as a necessary appendage for sharpening the points of the hooks! but a fly ought never to be dressed upon a hook which has not a good point; and if upon fair trial the point fail, the hooks are of bad quality, and should be altogether rejected. Hooks for dressing flies upon are to be preferred, if the shank taper towards the head, which adds greatly to the neatness of the workmanship.

The LIMERICK hooks are not usually straight, but form a curve, like the division of an intersected circle. This form is cer-

tainly objectionable, and will frequently, in striking a fish, be drawn from its mouth without fixing the barb, as may be readily conceived by an inspection of the plate: add to which, the barb projects from the point too abruptly; which, if the fish do not rise very freely, will prove a source of mortification to the Angler, as he will frequently scratch their mouths, without firmly hooking a single fin.

The common LENDAL hooks are of good form, but the distance of the extreme point from the barb is for the most part too great; neither do the barbs project sufficiently. In many instances these hooks may be found so nearly resembling a bent pin, that they may be introduced into the fleshy part of the hand, and drawn back, without inflicting pain. How then can they be expected successfully to resist the active exertions of an irritated Trout, struggling for liberty in its

own element, which the want of a proper barb tends to render easily attainable by enlarging the orifice, instead of securing to the Angler the anticipated prize?

The SNECKBEND, as it is commonly called, diverges from the parallel lines from the bend upwards, and the point is frequently near an eighth of an inch to the right or left of the shank of the hook.

By some persons this form is preferred, but their judgment is certainly erroneous; for it frequently happens that the fish discovers the deceit, or in rising short, misses the artificial fly; the Angler very naturally strikes at that instant, and will very often scratch the fish, owing entirely to the lateral projection of the barb, which, if it were level with the shank, would almost invariably be avoided.

The straight KIRBY hooks approach the desideratum, in shape and temper, nearer than any other manufacture; (vide PLATE II. fig. 4) unless the Kendal hooks could be improved in the form of the barb, and divested of the superfluous length of point; in which case they would be upon an equal footing.

These remarks will probably meet with opposition from prejudiced Anglers, some of whom may be deemed skilful in the art; but, as they have not been hastily or partially framed, it is hoped the beginner will profit by adopting them, in preference to the partialities which habit may have rendered familiar to those who have practised for years.

OF

GUT AND WEED.

The directions which are necessary for chusing these materials are very simple. Those lengths are most to be preferred which are bright, round, hard, white, and even or of equal circumference.

For discoloured water it may be necessary to stain the gut; but in clear water, ocular demonstration will prove that *white* is the least perceptible colour: a few recipes for staining different shades will, however, be attached to this article.

For beginners, or where the fish are of large size, gut is preferable to hair, as affording greater security; but in fine bright waters, a good round single hair will manifest a decided superiority in raising fish; and the

delicate skill required for the management of them when hooked enhances the pleasure of the experienced practitioner.

Indian weed is sometimes recommended to the Fly-fisher; but its extreme brittleness is a great objection, as it requires at least an hour's soaking before it becomes sufficiently elastic for use.

The following methods of staining gut were given to the author as choice and valuable recipes, and their efficacy is indisputable; but as they are to be found in Taylor's Art of Angling, and the Driffield Angler, their claim to originality falls to the ground.

For a brown.—Boil pounded alum until it dissolves, add a quantity of walnut tree bark when the sap is up, or the nuts of the same tree whilst in the green state; boil them

together for nearly an hour, and let the liquid stand until nearly cool; skim it, and put in the gut or hair for about a minute, until you perceive that it has imbibed the colour intended. If it remain long, it will be tinged too deeply, and the gut will become rotten.

For a pale watery green.—To a pint of strong ale add half a pound of soot, a small quantity of walnut leaves, and a little alum; boil them together for about three quarters of an hour, and when nearly cold put in the gut or hair.

The following recipes have not been made so generally public, but are much more simple, and equally effectual with the foregoing: viz.

Stain your gut in strong tea lukewarm, with the addition of a small quantity of

logwood scrapings, for twenty-four hours, and it will be an excellent colour; or another equally common beverage, Coffee will, if made strong, by the assistance of a little alum, impart a fine brown colour to the gut or hair.

OF THE REEL.

Although the multiplying reel is now in general use, the advantages which are set forth in its favour are more than counterbalanced by the frequent disappointment which the Angler is liable to from its imperfections. The fact is that the power of the wheels, as now arranged, is inadequate to move a comparatively small weight at a trifling distance. To be convinced of the truth of this observation, it is simply necessary to fasten a piece of wood of a couple of pounds weight to the end of a reel line, and throw

it into the water, letting the line run out to a distance of twenty yards down a stream. On winding up the line, the person who tries the experiment will be annoyed by the frequent stopping or catching of the wheels, as if the cogs were choked up; and it will not be without considerable difficulty that he succeeds in accomplishing his object. With respect to greater weights, when supported by animated resistance, it will be found almost impossible to succeed; and should a Salmon of tolerable size be hooked. and the line be attached to a multiplying reel, it will require the utmost skill and attention of the Angler, by occasionally drawing up the line with his left hand, and then winding it, to secure the fish; and this is the only remedy he has, for should he rely upon his reel, and persist in forcing the wheels round, the main pillar or support of the engine will certainly break, and leave him to ruminate upon his rashness.

On the other hand, the common plain pillar reels bear an even and steady pull upon the extreme weight, and though more tedious, they are more to be depended upon for certainty and security.

The multiplying reels possess the advantage of winding up, and letting out the line with greater despatch; and where the fish do not exceed half a pound in weight, they may be preferable; but a few seconds of time are not an object of consideration to the steady Angler, whose chief reliance is on the firmness and correct formation of his tackle.

An improvement in the principle of multiplying reels might be easily suggested, which would negative the objections before mentioned; and it is certainly surprising that they have not hitherto claimed the notice and attention of some ingenious me-

chanic, as their defects are almost universally complained of.

Some reels are fastened to the rods by means of nails, which is the most secure method; but, for the Angler who travels, they are made with a long hollow groove, which is fastened to the butt of the rod by two pieces of leather, passing over both ends of the brass groove: others have a ring attached to them, which is intended to be lined with leather, and passed over the point to the handle of the rod, where it is made fast by means of a screw. This latter mode is the least troublesome, and is perfectly secure.

OF

THE PANNIER.

The Fishing Pannier should be of neat light wicker work, broad at the bottom, and

narrowing towards the top, where the lid is fastened by means of a padlock, or wooden peg secured to the body of the basket by a piece of tape: the aperture in the top of the basket ought to be sufficiently large to admit, without the slightest degree of force or pressure, a Trout of half a pound weight. For Salmon fishers they are sometimes made of a different form, with ends projecting from the main body of the pannier, and so shaped as to contain a tolerably well grown fish at full length.

OF BOOKS.

Every Angler ought to be furnished with at least two pocket books. The one for containing his flies is composed of parchment, the leaves of which are separated at each corner by pieces of cork, so that the flies may be preserved from injury. The other for holding an assortment of every material necessary for dressing a fly is commonly made to suit the fancy of the proprietor, but should consist of numerous divisions; so that the hooks, hackles, furs, wings, and dubbings may be kept asunder, and yet so easily accessible, that the materials wanted may be found without delay.

In addition to the books, an Angler resident near a river, who has the opportunity of gratifying his inclination for this pursuit as often as he pleases, should have a small cabinet of drawers in which he may keep his furs, wings, &c. separate; for the constant additions which a provident fly fisher is continually making to his stock will soon render a book of little use. In one of the drawers should be fixed neat wooden rollers, for winding the various coloured silks upon; another should have divisions for hooks of different sizes; and the whole

ought to be formed of cedar wood, which, aided by the introduction of camphire, all-spice, alum, and tobacco leaves, will effectually preserve the feathers and skins from the injurious devastation of the moths; for without these precautions, the incessant attacks of these destructive insects would soon render the collection entirely useless.

TYING

OR

DRESSING FLIES.

Having enumerated and described the materials separately, the next object will be to treat of them collectively, as applicable to the purposes of the Angler, to whom nothing is of more importance than correctness in the size and colours, and neatness in the

formation of the artificial fly, which will therefore first claim attention.

Whether a common hackle, or a dubbed winged fly is to be manufactured, it is invariably necessary to have the whole of the materials which are to compose the imitations properly adjusted previous to the commencement of the operation. -- 1st, The Hackles stripped, or divested of the soft downy feathers which grow nearest the root, and turned back ready for twisting on the hook; see PLATE II, fig. 7 & 8, 2d. The Gut carefully examined, and tried by moderately pulling it in proportion to the weight expected to be held by it. This precaution will frequently save the Angler much disappointment, by discovering defects not apparent to the eye.—3d. The Dubbing properly mixed to the exact colour of the body of the natural fly, a small proportion of which should be moistened, and held up to

the light; for the camlets and furs, when wet, generally become several shades darker than when in a dry state, and in some instances assume a totally different hue.—4th. The Silk well waxed with a colour lighter than the body of the fly, and a hook cautiously tried as to temper, and prudently selected as to size.—5th. The Wings must be stripped from the feathers by an even but sudden pull, and for the instruction of the beginner representations are given in PLATE 11. fig. 5, 6, & 10, of the feathers before stripping, and their appearance when prepared for fastening on the hook.

Every thing being thus in a state of readiness, the hook must be first fastened to the finest end of the gut with waxed silk, beginning (if for a hackle fly only) at the bend, and working towards the head of the hook; when within about three turns of which, the hackle must be fastened in, and the winding

of the silk-continued, until it reaches the end of the shank: having reached this point, it must be turned again, as if to retrace the same ground for two turns, which will form the head of the fly.

The dubbing, if of fur or camlet, must now be twisted round the silk as in fig. 13, and wrapped on the hook for nearly half the proposed length of the body, when it may be fastened by a single loop, in order that both hands may be at liberty for the better management of the hackle. If the body is to be composed of peacock or ostrich harl, it ought to be fastened on at the same time with the hackle, so that it may be perfectly secure. Should the hackle be of tolerable size, there will be no difficulty in twisting it firmly on the hook with the fingers only; but if small, a pair of neat pliars which close together by a spring will be found of great utility in winding the turns of the

hackle close under each other; AND, if pliars be wanting, a piece of silk fastened to the end of the feather will answer the purpose.

When enough of the feather is wound upon the hook, the remainder should be pressed closely under the thumb of the left hand, and the fibres which may be entangled picked out by means of a needle. The silk with the dubbing must now be twisted over the end of the hackle, (which the left thumb kept down) until the body of the fly is of the length required, taking care that it never proceeds beyond the bend of the hook, which would give it an unnatural ap-A single loop will keep the pearance. whole together until the dubbing be picked out, and the hackle properly arranged, when the fastening off must be effected, by making three or four loose turns of the silk at such a distance from the hook, as to admit

of the end being passed under them, as shewn in PLATE 11. fig. 9.

The loose turns must then be wrapped closely on the hook, and the end drawn tight, which will so completely secure the fastening, that if neatly managed, it will be difficult to discover where the fly has been finished. This mode of fastening is called the *invisible* knot.

In making a winged fly the same method may be observed with respect to whipping the hook to the gut, as far as the fastening in the hackle; after which, instead of returning immediately with the silk in order to form the head of the fly, the wings must be fastened before the dubbing is wound. Some persons fix the wings to the hook with the root nearest the bend, and force the points or narrow ends of the fibres back afterwards, making use of the short remains

of the roots to effect the division of the wings. This method is however tedious, and difficult to be understood by a young practitioner.

The most simple mode of proceeding is to fix the wings on the shank of the hook lengthwise, with the narrowest ends nearest the bend, fastening them by three or four turns of the silk above or nearest the head of the hook, and then cutting the root ends close with a small pair of scissars; after which the silk must be brought below the wings, and the body twisted for a short distance, as in the hackle fly.

The hackle must be wound once round the hook at the head, which will conceal the ends of the cut fibres, and add greatly to the neatness of the fly. If the wings are to be divided, they may be separated equally by a needle, and the hackle brought down between them, (vide fig. 11) and wound again round the hook for two turns below, where the silk will be found in readiness to fasten it.

If it be not necessary to divide the wings, after making one turn at the head with the hackle, it should be brought immediately below them and twisted as before. The fastening off is to be managed in the same manner as in the common hackle fly: but it is almost impossible to convey clear instructions for the dressing of a fly, as particular circumstances or materials may occasionally require a different process, which the invention of the operator will best suggest. is strongly recommended to the beginner attentively to watch some skilful Fly maker, and in the progress of his work make such inquiries as he may deem requisite; from which greater facility and neatness are to be acquired, than from any written description whatsoever. The remarks upon tying flies

being thus concluded, the reader is referred to PLATE II. fig. 14 & 15, which exhibit a hackle and winged fly as they appear when finished.

But before quitting the subject altogether, the writer cannot avoid expressing a wish that, for the benefit of those who are not disposed to direct their attention to this branch of the art, the makers of Artificial Flies for sale would devote as much care to the firmness and security, as they do to the neatness of their workmanship, in which, (as exhibited at some of the tackle shops in London and Dublin) it must be acknowledged, no one can surpass them. It is however frequently the case, that after a few throws of the line, some part of the materials gives way, and the bare hooks remain openly exposed to the passing "inhabitants of the liquid element," much to the mortification of the person using them.

THE young ANGLER being now furnished with every requisite as enumerated in the foregoing pages, will anxiously proceed to the banks of some river in order to try his success.

His rod must be so fixed, that the rings may remain in a straight line from the handle to the point. The reel, with the line wound upon it, of such length as the breadth of the water may require, must be fastened firmly under the butt of the rod, so that the handle may be on the right side; for, if it be above, the rod will never play correctly. The line being passed through the rings, a loop should be fixed to the end, and the taper foot line of twisted hair attached thereto, to which the gut, which ought to be at least three yards in length, is to be fastened.

An experienced Fly-fisher will use three, or even a greater number of flies at one time. The point fly, which should be fastened to the foot line by a water knot in preference to a loop, must invariably be the largest, or the line cannot be thrown neatly. The first dropper should be placed at the distance of a yard from the point fly, and fastened by a loop close to a knot in the gut line: the length of this dropper may be about three inches.

The second dropper, which should be smaller than the first, is to be fastened within eighteen inches from it—length of the gut about four inches and a half; and if a third be required, the distance should not exceed a foot from the second, and the gut on which the fly is whipped should be longer than either of the other droppers, in order that they may all play upon the water together, without sinking the main line. It will however be generally found that three flies are amply sufficient, and most frequently it is

best to have the point fly winged, and the droppers hackles.

When a novice first attempts to throw a line, he must begin with a short length, which can be encreased as he finds the management of it become easy to him. Care must be taken that in passing the line behind the back, it be permitted to attain the full extent before any attempt is made to return it; for if this point be not strictly attended to, the end fly will crack off at every throw: to avoid which, it is recommended to begin by throwing the line without any fly for a short space of time, until the proper management of the rod is acquired; and afterwards to angle with the point fly only, until such proficiency be attained as may authorize the addition of the droppers.

In Fly-fishing the person who is most expert in throwing a considerable length of line, and has a quick sight, and obedient hand for striking, will be the most successful.

To keep as far from the bank as possible is particularly desirable; and if the wind be at the back of the Angler, and his shadow prevented from appearing upon the water, so much the better.

The principal object in throwing the line is, that it may be extended in such a manner, that the point fly may first lightly touch the water, without disturbing it in a greater degree than the actual alighting of the natural fly. Throwing the fly directly opposite, or rather above the Angler, and playing it gently across the stream as it floats downwards, is most to be recommended; for to force it against the current is unnatural, independent of the ruffling of the water which such a bad practice occasions; and which, instead of alluring, will infallibly frighten the fish.

The moment of the water being disturbed or ruffled by the fish rising must be carefully watched for by the fisherman, as at that critical instant he must strike, in order to hook his prey; for the fish having discovered the deceit, the least delay will enable it to escape. A very slight inclination or turn of the hand is sufficient to fix the barb of the hook, as, if too great violence be used, the hook or line will be greatly endangered, and the water disturbed by the mad struggles of the lacerated sufferer.

If the fish be of good size, and the hook be firmly fixed, the first consideration is to keep the rod upright; or even, by forcing the butt forward, to throw the point of it over the shoulder of the Angler, which will tend greatly to fatigue the fish, if it should not be necessary to give it additional line from the reel. When found to be sufficiently exhausted, it must be either taken out of the water by means of a landing net, or drawn on to a shelving gravel-patch or bank.

When the rod is greatly agitated by the struggling of the fish, it is advisable to give it a greater length of line, as it may be presumed that the size of the struggler is greater than common, and the additional weight of line, besides giving facility to the Angler, and easing the strain upon his tackle, will more speedily exhaust the power of the fish, and render it an easier captive.

When a Trout is observed to rise of his own accord, the flies must not be thrown directly over him, but about a yard higher in the stream, so that they may float down to his view, without the fear of agitating the water; and if upon hooking a fish he be observed to leap frequently out of the water, it will require the utmost care of the Angler to secure him, as he may calculate upon the

barb being only slightly fixed; on the contrary, if the fish remain below the water and struggle at the bottom, there need be little fear of his escaping, as the hook will be found to be firmly fastened.

odi e iz vanije

Although many persons have ridiculed the idea of attention being paid to the colour of the dress of an Angler, it is certainly of some importance to avoid glaring or bright colours, and above all metal buttons. A dark bottle-green, as approaching nearly to the colour of the earth and foliage of the trees, is to be preferred to any other shade. Any recipe as to keeping the feet dry would be misplaced amongst directions to the keen fisherman; for the advantages of wading and crossing the stream are so frequently manifest, that few young persons can be deterred (by the mere fear of wetting their legs) from endeavouring to participate in the diversion which the wader will almost con-

stantly command, by being enabled to throw his flies under bushes, and over the most secret retirements of the objects of his amusement. Some persons, it is true, hold out objections to this practice, by bringing to imaginary view rheumatism and agues, in their most dismal colouring, as the consequences of such an act; but, whilst the body is in exercise, little is to be apprehended from these objects of terror. Many instances might be brought forward in corroboration. of this assertion, in the persons of men who have followed this practice from youth upwards, and arrived at extreme old age. without having experienced the slightest inconvenience or ill consequences from the daily immersion of their legs.

To remain long in one station is reprehensible; and it is absolutely necessary to substitute dry clothing for such as may have become wet by the operations of the day, immediately on arriving at the house of rest or refreshment. With these precautions the Angler may, if possessed of a good natural constitution, bid defiance to the effects of the element, which his prejudiced or timid friends would set forth as objections to deter him from the perfect enjoyment of an innocent and favourite amusement. If situation or other circumstances should render it unpleasant, or not easily practicable to the wader, every time he hooks a fish to draw it to the shore, he will find that, after played with for some time, by pulling it with an even but somewhat rapid motion, it will be incapable of much action on reaching his hand; so that he may without difficulty extract the hook, and lodge the fish safely in his pannier, before the temporary stupefaction is removed.

In fishing in the evening, it will occasionally happen that bats and swallows mistaking the artificial for the natural fly, will hook

themselves, instances of both having occurred to the Author more than once; and the celebrated Angler of the Dee, John Edwards, has assured him, that on one occasion whilst fishing rather late with one of the moths, he hooked an owl, which after a long struggle he succeeded in securing!

Proper Zeasons and Times for Angling.

Before proceeding to treat of the haunts and descriptions of the Trout, &c. a few remarks on the seasons and most favourable times for Angling may not be here misplaced.

Although fish are to be taken with the Fly in every month throughout the year, which the writer of this treatise, by way of experiment, succeeded in proving, yet but little diversion is to be expected until the beginning of March; unless indeed the Spring be unusually early, and the weather

warm, in which case the fish run sooner, and sport may occasionally be met with in February. But until the snow water disappears entirely, and the severe night frosts discontinue, the Angler cannot calculate with any degree of certainty upon meeting with much amusement.

Easterly and northerly winds in the Spring and Autumn are generally unfavourable to sport, as the fish resort to the deep pools for a greater warmth than is afforded them by the shallow streams, where they remain at the bottom, afraid to encounter the severity of these piercing blasts: but in the Summer, if accompanied by a cloudy atmosphere, good diversion may be obtained with the wind in these points.

A warm breeze, if not too violent, is at all times favourable to the Fly-fisher, particularly if Salmon be his object; for which purpose the hours from eight till eleven in the morning, and from three until six in the evening, are most eligible.

After a clear bright night, if the day be dark and lowering, fish usually rise freely, having been prevented from roving in search of food by the brightness of the moon; so on the contrary, after a dark gloomy night, but few good fish are to be taken until the approach of evening, as having been glutted with the moths and other varieties of insects, (which the night produces in almost as great abundance as the day) they are not upon the watch for food, but retire to their holds. When the waters have subsided after a FLOOD, and are beginning to assume their natural colour, an opportunity is presented to the Angler, which he ought on no account to let slip, as he is almost sure to meet with excellent diversion, unless it happen to be in shearing time or the hay harvest; for, in the former case the fish are uncommonly shy, having been frequently deceived by mistaking the particles of wool which the current brings down for their natural food; and in the *latter*, the grass and hay which (if the river pass through meadows) cover the surface of the water will prove so troublesome, that the pursuit is most commonly unsuccessful.

The best times of the day for Fly-fishing, as before mentioned, are morning and evening; but when the rivers and brooks become narrow and low by long droughts, it is of little use to attempt this method. In such state of the water, the most successful way of taking Trout is by means of a pair of wings made from the feather of a Landrail, or the mottled feather of a Teal, with a well-cleansed Gentle fixed upon the hook; which bait proves very alluring, if sunk about two inches under the water.

OF

THE SALMON.

As this beautiful and delicious fish spends a considerable portion of its life in the sea, it can be hardly with propriety considered a fresh water fish; yet, as it is to be found in most of our rivers which have direct communication with the Ocean, and as it is productive of such very superior diversion to the Angler, it has been generally usual in treatises of this description to give it precedence as the KING of FISHES.

Inasmuch as the use of the fly surpasses every other mode of Angling, in the same ratio is the Angling for Salmon superior to common Trout fishing. The following extract, as being in unison with the ideas of the Compiler, he has ventured to copy from the Edinburgh Encyclopædia. Under the

article Angling is observed:—" It is most common, before a person becomes a Salmon Angler, that he has passed his novitiate in Trout fishing; yet even then, he will require a few instructions for the prosecution of this more important and delightful branch of Angling.

"Composure, patience, and perseverance are indispensable qualifications for all the followers of this art, but more especially for the Salmon Angler. He must lay his account with frequently beating the waters in vain exertion; in being long wet and weary, ere he can (to use the fisher's expression) move a fin; and when he does, to be perhaps then only mocked with a wanton rise, or a false bite; or should he at last prevail in luring the Salmon to his fly, and after working and playing him through many streams, and through many pools, he brings him within his reach, and then thinks he is

to take possession of his prize, in a moment the tackle snaps, and all is gone. Such, with many other disappointments, await the Angler; but these ought not to make him fretful, nor give up the pursuit; he must persevere in hopes of better sport. In this point of view, the course he has to steer is a fine practical lesson in the economy of human life.

"Many writers on Angling have given various directions for the dress that should be worn, how to counteract the effects of moisture, and what drink to take while you are employed in this amusement. These are pincipally to use water-proof boots and shoes, and, to make them the more secure, to lard them well with mutton suet, in order to keep the feet and legs perfectly dry; to sit upon a piece of coarse woollen cloth, doubled two or three times; and while warm, to avoid the drinking of small liquors. Such

advices may well suit float and gudgeon fishers, but the Salmon Angler must laugh at such ideas he had better indeed never begin the occupation, if he has not a constitution strong enough to wade in deep and rapid rivers, during all the hours of the day, and be able to bear every vicissitude and eager extremity of both sky and water.

"As the spirited and skilful navigator does not lie in a harbour waiting for a favourable wind, but goes to sea to seek for one, so the keen and knowing Angler does not sit at home to watch for a fortunate prognostication, or change of weather, but takes it as it comes, and repairs to the river to ply his skill in rousing the finny race to his artful lures. There is scarcely any time, unless when it thunders, or when the water is thick with mud, but you may chance to tempt the Salmon to rise to an artificial fly. But the most propitious and critical moments are un-

doubtedly when clearing after a flood, the water has turned to a light whey, or rather brown colour; when the wind blows pretty fresh, approaching almost to a mackerel gale, (if not from the north) against the stream or course of the river; when the sun shines through showers, or when the cloudy rack runs fast and thick, and at intervals discovers the fine blue ether from above. In these situations of the water, and of the weather, you may always depend upon excellent sport,"

Although Salmon are partial to a cold climate, and are not to be met with in the Mediterranean, or warm latitudes, yet they are seldom to be found in quantities in rivers which are liable to be completely impeded by the severity of frost. Our own kingdom seems most congenial to their inclination and nature; for as before observed, they are to be

caught in almost all our streams which are near the sea.

The time of spawning varies in different rivers. At Newcastle-upon-Tyne, these fish are in season at Christmas; whereas in the Welsh rivers, they do not begin to run until May or June. After they have been for a few days in the fresh water, they are for the most part in high season, and a well grown fish at this time is a valuable prize to the Angler who may be so fortunate as to secure him.

When on feed the Salmon generally takes up a position at the foot of a strong stream which terminates in a whirlpool or eddy, and the most successful bait which can be used is the artificial fly. Those made in imitation of the Dragon flies are the most to be depended upon, as these insects are constantly hovering over the water, consequently are more

familiar to the view of the fish. They are however so capricious, that they will not unfrequently rise at an extremely gaudy fly, which bears no resemblance to nature, in preference even to a real wasp or Dragon fly; and it will sometimes happen that a Trout-fisher with small flies, will succeed in raising the fish immediately after an Angler prepared for Salmon-fishing has thrown over the spot a dozen varieties of large flies. The best hours of the day for this diversion are from eight to eleven in the morning, and from three until six in the evening. For specimens of Salmon flies, see PLATE 111.

In Trout fishing when Salmon frequent the streams, it is necessary to use stronger tackle than might otherwise be advisable. An instance of the utility of this precaution occurred to the author. In one morning's fishing, five Salmon rose at his Trout flies, two of which he succeeded in taking: the

largest weighed sixteen pounds and three quarters, and measured two feet nine inches in length. It is true the gut of which the line was composed was choice, but it was single, and not of that description which from its extreme thickness is called Salmon gut. The time occupied in playing this fish was about an hour and three quarters; and never did a General derive greater satisfaction from a victory than was felt on that occasion.

If the multiplying reel be reprehensible in Trout fishing, it is absolutely useless where Salmon is the object, as the exertions and activity of this fish will try the strength of the tackle in all its points. When hooked, the Salmon generally darts with violence up the stream, and with extreme velocity: at this time it is not advisable to let much of the reel line out, but if possible, by forcing the rod well back, to keep with the fish by

running along the side of the river. On reaching the head of a current, it will probably throw itself out of the water several times, apparently with an intent to break the line with its tail. It may now be necessary to humour the efforts of the fish by giving a little additional line, to ease the strain which this repeated violence may occasion, but as soon as opportunity offers, it must be wound again upon the reel. Disappointed in these fruitless efforts, and maddened by the disappointments, it may probably return with encreased velocity to the spot in which it was hooked, having reliance on some strong hold or secret haunt in the vicinity of its feeding ground. To prevent this, it now requires all the Angler's skill and attention. by endeavouring to turn the struggler as frequently as possible, which will fatigue it more than any other expedient. If the tackle will not admit of his bearing upon the fish, a few small pebbles thrown before its

head, so as not to endanger the line, will generally produce the desired effect; and if it so happen that it becomes sulky, and sinks without motion to the bottom, this is the only method to be employed to rouse it into action; for a fish should never be permitted to remain quiet after being hooked. As it becomes exhausted, it may be easily drawn by degrees on to a gravel bank, for within reach of the gaff, when the anxiously earned prize is made secure. If when taken out of the water the colour of the back he blue or inclining to black, the fish is in high season—if reddish, approaching to brown, it is kipper and good for nothing.

The male fish is frequently found with a horny proboscis projecting from the under jaw, with which he roots in the gravel in order to form a hed for the spawn of the female. This being deposited, they both proceed to cover it with the loose gravel; to

in two continuous is in

secure it from the voracity of the Trout and other fish, which are particularly fond of this food, and follow the Salmon in shoals, in the expectation of partaking of it.

The young SALMON FRY, or SAMLETS, are generally first animated in February, when they direct their course towards the sea, occasionally halting in favourite spots. On reaching the brackish or salt water, they stay for about a fortnight, in which short space of time their growth is very rapid.

They are extremely voracious, and afford excellent diversion to the young Angler, as he will not unfrequently have a fish at every fly at the same moment. Although they are a delicious fish, a moment's reflection of the injury done to the river by the destruction of so many young fry, which in a year or two would be so much better worth taking, after having multiplied their species in an

extraordinary degree, ought to deter the Angler from continuing his sport when he finds a shoal of them.

But the injury which is occasioned by the rod and line is insignificant when compared with the wilful slaughter caused by mild weirs, where in one night a cart load of these little fry may be taken. : The gentlemen through whose estates the river winds ought to be particularly, attentive to those most to be dreaded ravagers, occurrens or MILLS who in a flood, (at which time the fry run in shoals) under the pretence of setting baskets for eels, fix them in such a manner as not to admit the possibility of a single fish of any description escaping, however small it may be; and they have been known to catch such immense numbers of samlets, that for want of knowing what to do with them, they have been under the necessity of throwings them to the pigs. (becall one real) ini)

THE TROUT.

Of all fresh water fish this is the most beautiful, and, next to the Salmon, is most esteemed by the Angler for the diversion it affords. The form of the Trout is long in proportion to its breadth; having the head round, and sharp teeth in the tongue as well as in the jaws. When in perfect season it is thickly studded with red and black spots, which relieved by the dark olive of the back gradually mixing with the rich yellow of the sides and belly, produce a fine effect. At this time it is hog backed like most other fish.

The variety in the shape and colour of Trouts which are taken in different rivers and pools, has induced some persons to imagine that there are three distinct kinds of this fish; viz. the RED, the YELLOW, and the WHITE, the former of which ranks highest in estimation; but the more generally received and most probable opinion is, that this difference arises from the quality of the food, or from the water which they inhabit being impregnated with some substance capable of producing this effect. Certain it is, that their haunts, voracity, and modes of feeding, are every where alike.

They spawn about the latter end of October or beginning of November, at which time they are unwholesome and not worth eating. At this season they constantly work up the stream in order to find proper situations for spawning, for which purpose they generally prefer brooks, where gravel or sand mixed with small stones abounds, in which they root a bed for this deposit. This being effected they appear quite exhausted, and wasting away become soft and lean. In

this state they are attacked by a worm, vulgarly called the water louse, which they have not strength to rid themselves of until re-invigorated by the genial warmth of the sun's rays, on the approach of spring, when they quit the still deep water where they have remained inactive during the winter months; and revisit the strong streams, the force of which soon frees them from this disagreeable insect; which being accomplished, they speedily regain their activity and vigour, and in the month of May are in high season.

The favourite haunts in which the Trout delights, and where the Angler is most likely to meet with diversion, are the junction of two streams—the tails of currents—below bridges—near old weirs or pieces of rock—where the roots of trees are exposed by the bank having fallen in—under hollow banks; and an excellent mode of enticing a good fish is to throw the fly against the opposite

bank, so that it may drop gently from thence to the water; also, wherever there is a fall of water, or a whirlpool; as, when on the watch for food; they take post at the foot or sides of agitated waters, lying in wait for such flies, &c. as the motion of the element may drive before it.

In bright weather, when the water is low, another very successful method of taking Trout is, by means of a line of about a yard in length affixed to a short stiff rod, which will facilitate the dropping of the fly between bushes, and under the roots of trees. The best baits are the stone-fly, green or gray drake, and the down-looker or oak fly, in their natural states; by means of which, if due caution be exercised as to keeping from the view of the fish, the Angler will hardly ever fail to reap the reward of a handsome catch.

OR THE

GRAVEL FRY.

The history of this little fish, which is also distinguished by a great variety of other names, as the fingering, pink, gravling, LAST - SPRING, SKIRLING, FORK - TAIL, BRANDLING, SHEDDER, SAMPSON, and PAR, has not been hitherto explained in a satisfactory manner.

They are only to be found in rivers frequented by Salmon, and many are of opinion that they are all males, and are the dwarf or unnatural produce of the mixed spawn of the Salmon and the Trout; others that they are produced from the spawn of those Salmon, which being prevented from regaining the sea, become sick and incapable of the regular functions of nature.

On the sides of this fish are dark marks or streaks, such as would be left by the hand if immersed in colour, whence it derives the name of Fingering. Some contend that they hever exceed in length eight inches, or in weight a quarter of a pound; whilst others assert that, on visiting the sea, they change their form in some points, lose the dark manks on their sides, and return to the rivers several pounds in weight. In corroboration of their growth, a gentleman of the greatest respectability assured the compiler that he has frequently taken them from the river by means of a casting net, and turned them into a pool, through which the stream of a mountain rivulet passed, and that they throve wonderfully, and exceeded the weight of a pound in a short space of time. As opinions respecting this fish are so various, it is surprising that some experienced naturalist has not directed his attention to the observation

ear ear egg

of its haunts and habits, to settle the points in dispute.

These fish afford the Angler great diversion, as they will rise at the fly at almost all times; and even when the water is become extremely low by long droughts, or when the sun is shining in all his splendour, they may be taken in considerable quantities. They are of exquisite flavour, and if properly potted, the Char of our northern lakes is not to be preferred as a delicate morçeau for the palate of an epicure.

THE

GRAYLING

OR

umber,

like the Trout, delights in the streams of mountainous countries, but is by no means

common to all rivers which produce the latter, and it is rather remarkable that it is not to be met with either in Scotland or Ireland. The rivers in Derbyshire, Yorkshire, Shropshire, and Staffordshire, and the Dee which runs through a considerable portion of North Wales, will however furnish them in sufficient numbers for the Angler's amusement. In France and Switzerland they are found in moderate quantities, and are greatly esteemed.

The title of Grayling appears, to have been given to this fish from the gray silver colour of its sides; that of Umber to be derived from the Latin Umbra, a shadow, which the rapidity of its motions authorizes, inasmuch as when swimming, it darts with such velocity as to give the semblance to the eye of the flitting of a shadow, rather than the actual movement of an animated substance.

eved of helicante of the half of committee?

The Grayling is longer, and not so round as the Trout, and somewhat resembles the Dace in form: it seldom exceeds sixteen inches in length; has no teeth, but the lips are rough like a file. When in season, the back is of a dark colour nearly approaching to black, and the sides gray: the head is rather small, with prominent eyes. When first taken out of the water they have a peculiar smell, said to be occasioned by their feeding upon water thyme, whence the Latin name Thymallus is supposed to have been given to them. For flavour they are preferred by many to the Trout. They are most in season in the winter: but even at the time of spawning, which is in May, they do not lose their flesh and beauty as Trout and Salmon do. er valdbere elikalis or savinter lime

The haunts of the Grayling are in every respect the same as those of the Trout, and both will be frequently taken from the same

streams. They rise very freely at the fly, and are not easily deterred from renewing their attempts to seize the bait, even should they be unsuccessful in several trials, provided they do not feel the hook. Their mouths are so tender, that it will require the utmost caution of the Angler, after he has hooked his fish, to prevent the barb from breaking its hold. Most writers, in treating of this fish, have stated that it struggles but for a very short time, and is therefore productive of little diversion; but the contrary is not unfrequently the case, as they will struggle with extreme violence, until quite exhausted by their efforts to free themselves from the instrument which causes their distress.

The property and a property of the important of the contract o

el dili di e leo ell Gra din a che ell tres s

the conductor of RAINING and some

It is rather remarkable that this fish has escaped the notice of all our naturalists,

in circurate and in the

except Mr. Pennant; and it is not less extraordinary, that it should be found only in the rivers connected with the Mersey, in Lancashire. Mr. Pennant's observations on this fish, extracted from his "Journey to Scotland, vol. i. page 11," are here subjoined:

"In the Mersey near Warrington, (and in the river Alt, which runs by Sephton, Lancashire, into the Mersey near Formby) a fish called the *Graining* is taken, which in some respects resembles the Dace; yet it is a distinct and perhaps new species: the usual length is seven inches and a half, and it is rather more slender than the Dace; the body is almost strait, that of the other incurvated: the colour of the scales in this is silvery, with a bluish cast—those of the Dace have a yellowish or greenish tinge: the eyes, the ventral and the anal fins in the *Graining*, are a pale colour."

As they rise freely at the fly they afford

good sport to the Angler, and when in the humour it is not difficult to fill a pannier with them. They sometimes, though not commonly, exceed half a pound in weight, and are much better eating than the Dace. A small feather from the starling's wing, or a bright hackle from a golden plover dressed upon small hooks, will generally prove successful: Another very killing method is the sandy feather of a landrail dressed as for the wings of a fly, and a well cleansed maggot or gentle, as before mentioned for Trout. In the early part of the Spring they prefer worms, of which a small Brand-. ling and Gilt-tail are most to be depended upon.

THE

GRAY MULLET

is by no means common in the northern counties, and but rarely to be found in Scotland; whereas on the southern coasts it is the salt water, and will rise freely at the same flies as are used for Trout fishing, but if made rather larger the success of the Augler will be more certaint the writer having thus occasionally taken them near Rhyddlan Castle, where the rivers Clwydd and Elwy meet the salt water, whilst Angling for Salmon. These fish are strong in the water, and require care in the management of them, as they plunge violently.

The best time for Angling for them is when the tide is coming in, as when it abbst they return to the salt water. The head of this fish is of a depressed form, having the nose sharp; and the body oblong and compressed, on each side of the head below the nostrils there stands a little bone which is serrated on its lower part: the eyes are not covered with a skin; and there are teeth on the tongue and palate, but none upon the jaws.

รูปเมื่อเกรียนให้เกตรูการน้ำและ เมื่อ จนามแรง ทั้งใช้ - มีประชายายายให้เสียง **อักรับสา**สตร เมื่อได้การเกรียกก็จ

-and questioning most by the sale of the sale of the contract of the contract

should be the time that that the Sweet and the formation of the theory o

and open in a diving a modern of the contract of the contract

This is a leather mouthed fish, like the Carp; has a big head; and the body, which is long and rather round, is covered with large scales. They sometimes attain to the weight of four or five pounds, are a greedy fish, and will take all sorts of baits, but are sulky and inactive when hooked. The best mode of fishing for them is dibbing with a natural fly under trees or bushes, as they are fond of shady places.

The Chub delights in large rivers with sandy bottoms, and will frequently annoy the Trout fisher by rising at his flies; for as they make no play, and are good for nothing when caught, it must be considered mortifying to be plagued by them when in expectation of nobler game: in fact, in so little estimation is this fish held, that the French call it "Le vilain." To a young Angler they may nevertheless afford diversion; and being generally to be found of good size, they may be serviceable in preparing him for the better management of the more active objects, Trout and Salmon.

THE BLEAK

na salem e se in sale asia. A Salemengani salemani 1981

is a small delicate fish, scarcely ever attaining to six inches in length. The body is covered with thin silver scales, and the back is of a greenish colour. On account of their dexterity in catching flies, they are frequently called the water swallow. They are in season all the year except the month of May, which is the time for their spawning. As they are to be found in almost all our inland rivers, and as they are passionately fond of the small red and black ants, they are a good fish for initiating the young Angler in the art of Fly-fishing.

and the said of th

ลงสารณ์ตารแบบที่เกิดของได้ ตามสำคัญ เกิดและ ก็ร้อย (A

ROACE

AND THE

DACE, DARE,

or as is sometimes called the showler, will also rise at the fly greedily; but as they are so very generally known, a separate description of them is deemed unnecessary. By sinking his flies a little under the water, the Angler will find his advantage when fishing for ROACH.

This fish spawns in May, and it is easy to distinguish whether it be in season or otherwise; for if the scales upon the back be rough to the touch, it is out of season; if they lie flat and smooth, the reverse.

The DACE is a longer and narrower fish, and has smaller scales than the Roach, and spawns in March, which constitute the principal differences between them; as their haunts and manners are the same, and they are generally found together, each delighting in the deepest part of rivers where there is gravel or sand. Both afford sport to the Fly-fisher by their avidity in taking the bait; but as they do not require much skill to secure them, and are of so little esteem when taken, any person who has once participated in the pleasures of Salmon or Trout Angling, would feel dissatisfied with this diversion.

The fish thus described are believed to be all (worthy the Angler's notice) that are accustomed to take the fly as their natural food. It is true, instances have occurred of the Pearch, Pike, and even Eels, being taken with the artificial fly; but as such occurrences are uncommon, it would be inconsistent to class them with the fish mentioned in the preceding pages. It remains therefore to proceed to the description of the materials necessary to be used in the formation of the flies represented in the plates which accompany this treatise.

The author is aware that they can by no means be considered line specimens of the art of representing nature; but as they will convey some idea of the size and form of the natural fly, and may prove a more correct criterion for the imitator to adopt as to the colours of his materials than any written description, it is hoped that they will in

some degree prove useful and advantageous to such brethren of the Angle as may deem them worthy their inspection.

Robbert to mand growth all a red with the field

It may possibly be remarked that the number of flies selected is insufficient. Certain it is, that the ephemeral aquatic insects which the sun's genial mays animate in succession, are as endless in variety as they are incalculable in numbers, and may possibly all at one time or other serve as food for the Trout, &c. Yet to compile a treatise of this description would require the observation and deep attention of a Linnæus. Such therefore only as practical experience has pointed out to be worthy of selection are represented, and it is presumed they will be found sufficient to answer the purposes, and meet the wishes of the reasonable Angler.

Whilst upon this subject it may not be altogether irrelative to remark, that a good

will educate the education of reflects

treatise on the English water insects is much wanted; as most of the collectors of this branch of natural history, who have spared no trouble or expence in procuring foreign insects, are lamentably deficient in specimens of the description herein mentioned.

Accurately to enumerate the different names by which the several flies are distinguished would be impossible, as the neighbouring inhabitants of almost every river have different titles for the same insect. Such however as are known to be standard flies are given with references to their numbers, and the number of the plate. The remainder are no doubt well known to the experienced Angler by some denomination or other; but as name can add little to his information or success, when he has the representation before him, they will be described in the order in which they appear on the plates, as follows:

PLATE III.

contains specimens of five flies which will be found very successful in raising Salmon.

ស្រុកស្រីសេរ ស្រីស្សែស្រី

No. 1. is recommended as a spring fly, and is to be composed of the following materials: Wings, of the dark mottled brown or black-ish feather of a turkey; body, of orange camlet mixed with a little mohair; and a dusky red, or bright brown cock's hackle, plucked from the back where the fibres are longest, for legs; hook, same size as represented in the plate: and it is to be observed, that all large Salmon flies should be dressed upon two or three lengths of gut twisted together, and that the silk in dressing be brought beyond the shank of the hook, and wrapped four or five times round the gut, so that the sharpness of the steel may not speedily cut it.

PLATE 3



Digitized by Google ...

As the season advances, the same fly may be dressed with the wings of a brighter shade, and the addition of a little gold wire or thread wrapped neatly round the body at equal distances.

Note, wire or tinsel is to be preferred to thread, as they retain the lustre longer, and are more showy in the water.

No. 2. is of smaller size, and may occasionally be dressed upon very strong single gut. Any feather of a copper or dirty yellow colour, which is not too coarse in the fibres, will answer for the wings; such may be found on the domestic hen, turkey, or the landrail: the body of lemon coloured mohair mixed with a small portion of light brown fur or camlet; and a pale dusky ginger hackle over the whole. The main object to be observed in dressing this fly is, that the wings, body, and hackle, be as nearly as

Digitized by Google

possible of the same shade; from which, and being devoid of tinsel or any gaudy colours, it has been denominated the Quaker-fly.

No. 3. Although the colours of this fly are of a sombre cast, it is nevertheless frequently used in Summer with success. The wings are to be procured from the cormorant, or the mottled feather of the mallard, if very dark: body of dark sable ribbed with gold wire, over which a dusky red hackle should be thickly wound: for the tail, the mottled feathers of the drake; and before fastening off, a little flos silk should be unravelled, and fastened at the extremity of the work.

No. 4. differs materially from those preceding, and is given in order to describe the method of dressing *gaudy* flies; which, however fanciful or varied in shade or mate-

rials, will frequently raise fish when all the imitations of nature have proved unsuccessful: indeed so fastidious and whimsical are the Salmon at times, that the more brilliant and extravagant the fly, the more certain is the Angler of diversion. The fly thus given as a specimen is formed as follows: the wings the extreme end of the feather of a guinea fowl not stripped, but having the feather left on both sides the middle stem; a blood red hackle should be fastened on with the wings, and so arranged as to extend beyond them; the dyed feathers used by officers in the army answer very well for this purpose, if those from the macaw cannot be procured. The body is best made of the harl of an ostrich dyed to correspond with the red feather introduced; with a bright yellow hackle over it. The beautiful green feather which forms the eye of the peacock's tail should be fastened at the head, and left hanging downwards so as to cover

the body for nearly half an inch, and a few strips of the same part of the feather may be fastened at the tail.

In the dressing of the gaudy flies for Salmon the maker may exercise his fancy as he pleases, for it is impossible for him to be too extravagant in his ideas. The only caution necessary to be given is, that he should avoid introducing too great a weight of gold or silver wire, which will prevent the fly from being thrown neatly, and will cause it to sink too much under the water; for the same reason beads, which are sometimes used to represent the bright prominent eyes of the dragon fly, are reprehensible.

No. 5. is a copy from the common Wasp in the natural state, which has been selected as being a favourite with the Salmon peal, mort, or gilse; and well grown fish will sometimes rise at this fly in presence to any


other. It is to be made of the wool of a sheep or other animal dyed yellow, and a black hackle twisted at intervals over the body; or vice versâ, of a black body and yellow hackle. Wasps, bees, and hornets, are also the favourite food of Chub at particular times, and are to be employed with success in dibbing under bushes, &c.

Previously to commencing the description of the Trout flies, it is necessary to state that, although the greater proportion of those represented in the plates are common to all rivers, yet the time of their appearance will vary in different counties according to the temperature of climate, and forwardness or otherwise of the season. Correctness therefore in the statement of the periods at which they are usually to be found cannot be attained: the Angler's own observation will

be the best guide in this respect; and a very trifling degree of attention will soon enable him to distinguish each particular fly at a considerable distance, from the peculiarity of its flight, or other marked characteristic.

Although the imitation of nature is the principal object to be desired by the Flymaker, yet in some instances it will be advisable to enlarge or diminish the proportions of the artificial fly as the state of the water may require: for instance, if the river be very high, the fly may be dressed larger than nature; if very low, the size may be reduced, and the body made thinner than the natural fly appears; and in many cases the fly dressed as a hackle only, without wings, will succeed better than if made full by the addition of the feathers used for that purpose.

The colours of the flies will also in some instances, as in the stone-fly, duns, &c. under-



go considerable change as the season advances, generally becoming lighter with the progress of Summer: in this also the Angler's own observation must direct him.

Description of Flies in Plate IV.

No. 1. represents a dark fly with black body, which appears very early in March, and sometimes even in February; and as so few flies suitable for the purposes of the Fly-fisher are at that time animated, it is to be used with great success during the whole day. The body is made of dark fur to be obtained from a black water spaniel, or rabbit, with a very small proportion of claret-coloured camlet, merely to give the mixture a tinge when held up to the light; the wings from the back of the fieldfare or hen blackbird; and a dusky black hackle for legs.

No. 2. The Black Gnat

does not appear until nearly the end of April. The body is made with a black strip from an ostrich feather, and must be dressed thick, and rather short; the wings of a pale starling's feather; or it is equally neat if dressed as a hackle, for which purpose a pale dun is most suitable.

Although this fly is generally highly praised by writers on Angling, and by some has been recommended as a standard, or never failing fly, the character which it has obtained is infinitely too favourable. During several seasons in which the compiler made use of this fly, he observed that it was neglected by the fish if a grouse hackle was upon the same line; and that his other flies always proved more attractive than the black gnat. But, as it is a favourite fly with many

persons, and will certainly kill fish when the water is low and fine, to have omitted the description would have been censurable.

No. 3. The March Brown or Dun Drake.

This very excellent fly generally appears about the middle of March, and is strongly recommended as a good killer from eleven o'clock until three. Large quantities of these beautiful insects sail down the streams in succession, and invite the Trout to action. Their wings are upright on the body as shewn in the plate, and whilst they are on the water, it is almost in vain to attempt the use of any other fly; therefore as they vary in the shade of the body, it is advised to use three flies of this form, but of different sizes and colours at the same time, which will ensure success to the Angler.

The wings are made from the dark mottled feather from the tail of a partridge; the body of the fur from the hare's ear. intermixed with a small portion of yellow worsted, well dubbed together; a grizzled hackle for legs; and if the imitator chuse to be exact, two fibres from the same feather which composed the wings will enable him to form the tail. This appendage to the flies in their natural state need not be attended to in the artificial formation, as it is of little importance in aiding the success of the Angler; although, if flies are dressed for sale, it improves their appearance, and renders them more showy and attractive. may also be dressed as a hackle by means of the spotted feather from a partridge's back, using the same mixture for the body as before described.

No. 4. The Hazle Fly

is of a round form, and rather difficult to be imitated with success. It is to be used in May and June, and is very destructive where bushes abound. By some this is improperly called the Marlow Buzz. body is made of ostrich harl of two colours, viz. black and purple, which must be twisted very thick: the wings of the sandy coloured feather from under the wings of a throstle, or from the red feather of a partridge's tail, provided it be not too dark; a bluish hackle twisted tolerably full will answer for the under wing, as well as for the legs. The Cow-lady flies are also made in this manner, substituting a red or black hackle for the dun, and reducing the size of the fly very considerably.

No. 5. The Great Wark Dun

is one of the earliest flies which appear upon the water, and may be used in February, if the weather be mild. It has four wings, which are to be imitated by the dun feathers from the wing of a wild mallard which have a brownish tinge: the body of dark fur from the mole, mixed with a little dark brown mohair; and a dark grizzled hackle for legs.

This fly may be used during the whole year early in the morning, if the wind be high, and is often successful in raising Salmon.

No. 6. The Stone Hly

is found near the edge of shallow stony streams, and is a favourite article of food to the Trout, so long as it continues in season. It is hatched from a cadis, and issues from the shell before it has completely gained the use of wings. The usual time of the Stone fly's appearance is in *April*; but Salter, in his excellent little work on Angling, gives the following account of his success with this fly at a much earlier period:

" The general opinion, that it never appears until the middle of April, is a mistaken one; the reason that induces me to trouble you with this digression is to remove the error, by stating a circumstance that I have met with. On the eighth of March, when sitting by the side of a stream to repair my line, I observed a Stone fly crawling on the gravel: the appearance of a stranger so unexpected (in a cold day) excited my curiosity so far as to make a trial of an artificial one; the result of which was very great diversion from half-past eleven till one, when the Trout ceased rising to it. It was on a deep slow stream that is generally tinged with turbury water: but I never have found so much success with it upon rapid streams so early in the season."

This fly is the largest of the representations given, being an inch in length, and large in the body. The wings, which are

four in number, should not much exceed the length of the body, and are to be made to lie flat; the mottled feather from a hen pheasant or pea hen is best adapted to this purpose. The body is composed of any dark brown fur; such may be procured from bear's skin, or the dark part of the hare's ear, &c. and is to be mixed with yellow camlet or mohair, so that it may appear most yellow near the tail and belly of the fly; with a grizzled hackle of good length wrapped under the wings. Some persons, in imitating this fly, add two hairs from the beard of a black cat, or from the tail of the fulmart, or polecat, as representations of the horns; but, as before observed, attention to such minutiæ is unnecessary.

Another very general mode of dressing this fly is, by means of a long fibred grizzled hackle from a cock's back, without wings. It is also a deadly bait used in the natural state by dibbing under bushes; and must, in common with all large flies, be invariably used at the point.

No. 7. The Mealy Brown or Fern Fly


appears in May, and is an excellent fly for Grayling. It has four wings, which are made from the under part of a throstle or fieldfare's wing: those feathers should be selected which have the yellowest tinge. The common hen is sometimes to be met with of this shade, in which case her feathers may be used. The body is of dusky orange, which the light brown fur from a fox's breast will furnish; and a pale dun hackle for legs. Attention must be given to the division of the wings, which should stand as shown in the plate.

No. 8. The Blue Bun

is, in appearance, one of the most delicate insects which frequent the water; it is therefore extraordinary that it is to be found in the greatest quantities on cold windy days, being hardly ever to be seen in mild warm weather. It is an early fly, making its appearance about the first week in March, at which time it remains on the water during the whole of the morning. It is extremely difficult to meet with a feather of the exact shade, or sufficiently delicate in the fibre for the wings of this fly; it is therefore better to make it of a pale blue dun hackle, and use it as a dropper. The body is composed of the blue fur from a water rat, mixed with a small proportion of lemon coloured mo-As the wings of this fly stand erect on the body, a cock's hackle is preferable to that of a hen, not being so liable to yield to the action of the water.

PLATE V.

No. 9. is the representation of another variety of the Duns, being somewhat smaller



than the last. It is to be found about the latter end of May, and is a good morning fly. The body of mole-skin, or the fur from a black greyhound: the wings, which are four in number, are to be dressed in the same form as No. 7, PLATE IV. and are made from the feather of a starling; and a reddish ginger hackle for legs. This is also a good fly for Grayling.

No. 10. The Grange fly

has four wings made from the blue feather of a mallard-teal. The head is of the dark fur from the hare's ear; the body gold coloured mohair mixed with orange camlet, and a little brown fur; a small blue cock's hackle for legs. This is an alluring fly to Salmon mort if dressed rather larger than the representation; and on a smaller scale, none better can be found for the Salmon fry.

No. 11. The Cow-dung Fly.

Although this is not an aquatic insect, being most commonly found amongst the excrement of animals, it is nevertheless a favourite of the Trout; and when high winds have blown these flies upon the water, the Angler may calculate upon good diversion if he make trial of them.

They appear in March, and will raise fish until September. The body is made of yellow camlet or mohair, mixed with a little brown bear's fur, which gives the whole a dusky appearance; the feather from the wing of the landrail for wings; and a ginger hackle for the legs. The wings are to be dressed flat on the back, and the body made full.

No. 12. The Wellow Dun

is a beautiful insect, and is to be used in the morning and evening during the months of April and May, and again in September. The body is made of yellow yarn unravelled, (if martin's fur cannot be procured) and mixed with a little pale ash-coloured fur, which may be obtained from a fox-cub near the tail; the wings from the under part of a snipe's wing, and are to be made upright; with a pale dun hackle for legs.

No. 13. The Cream-coloured Hly

is an excellent bait for Grayling, and may be used from May until the end of August. The wings stand upright, and are to be made of a hen's feather which approaches to the colour of yeast; body dark blue fur; and a pale ginger hackle for legs; or it may be

dressed with a cream-coloured hen's hackle over a blue body.

No. 14. The Warry Long Legs

is a Summer fly; and although its merits have been underrated by many Anglers, it is an excellent killer on a cloudy day, when there is a good breeze. The body is dressed of brown bear's fur, mixed with the dark dun from a mole's skin; the dark mottled feather of a partridge for wings; and a brown cock's hackle of good length for the legs: wings upright and body taper.

No. 15.- The little Kron-blue Fly.

These flies are rarely to be seen in mild weather; but during the month of May they frequent the water in considerable numbers on cold windy days. They may be ranked amongst the smallest of the insects necessary


for the Angler's imitation, and can scarcely be dressed too fine. The wings are upright, and best made of a feather from under the cormorant's wing; as however it may not be an easy matter to procure one of these birds, and as one bird affords only about a dozen of the feathers requisite, a substitute is recommended in the tail of the tom-tit, which is nearly of the same shade. The body pale blue fur warped with purple silk, a small portion of which should be neatly picked out to represent the legs of the fly, as the use of a hackle for this purpose in minute flies is incorrect.

No. 16. The Grabel or Spider fly

is first seen about the middle of April, at which time the gravel in which these insects are bred is literally covered by incalculable numbers of them. They are extremely delicate, and not often visible on cold days; on which however success is more probable with this fly, than when they are to be found in such large quantities. They may be used from morning until evening; and the Trout are so passionately fond of them, that they gorge themselves with their favourite food, and retire to their secret haunts, thereby disappointing the most skilful endeavours of the Angler.

It is probably owing to the short duration of these flies that the fish are so greedy in devouring them, as they are seldom to be found at the expiration of about three weeks from their first appearance. The wings are made of the feather from the wing of the cuckoo's mate, the goat sucker, or in the absence of the preceding two, from the woodcock: the body of lead coloured silk for the lower and middle parts, and a strip of black ostrich harl for the thick part near the shoulders; round which a small dark

FPIP



grizzled hackle should be twisted twice, and the fly is completed.

PLATE VI.

No. 17. The Granam or Green Tail

is to be found on the water at the same time of the year as the spider fly, and is used with success early in the morning and late in the evening, whilst it is in season, which is rarely for a longer period than ten days. It is also a delicate fly, and not often out on cold days. It derives the name of Green Tail from a bunch of eggs of a green colour, which drop on the water at the moment of the fly's touching that element. The wings lie flat on the back, and are made of the shaded feather from the wing of a partridge or hen pheasant; the body of the dark fur from a hare's ear, mixed with a little blue fur; and for the tail the green harl from

the eye of a peacock's tail is the most showy material, although a small quantity of bright green wax (about the size of a pin's head) attached to the hook is the best representation of nature; a yellow grizzled hackle should be used for the legs; or it may be dressed as a hackle, with the shaded feather from under a woodcock's wing over the same body.

No. 18. is a representation of the Green Tail as it appears when on the water; the preceding fly having been drawn with the wings expanded for the purpose of shewing the colour of the body.

Ao. 19. The Hawthorn fly

is so called from being usually found near the shrub of that name. It is a good killer, and may be used from the middle of April to the end of May, from ten o'clock until three. The wings are transparent, and may be made from the palest feather of a snipe or mallard's wing: some use horn shavings, or the hard substance which is found in the core of an apple, for this purpose: the body of black ostrich harl; and a black hackle for legs.

Ro. 20. The Zummer Bun

is thicker in form than the generality of the dun flies, and is to be dressed upon a hook with a short shank. The body of the fur from a mole ribbed with ash-coloured silk; the wings from a wood-pigeon; and an ash-coloured hackle for legs. A good fly during the Summer months, in large waters.

Ao. 21. The Black Harl fly

is also a Summer fly, and is a good killer in warm weather early in the morning. The

body is of ostrich harl dressed thin, and cut close; the wings, which are four in number, from the pale feather of the starling's wing.

Ro. 22. The Orl fly

has every appearance of being produced from a cadis, and by some has been called the BROWN CADIS FLY. The body is large, and is successfully made of that part of the peacock's tail feather which is perfectly free from a green cast; the wings from the feather of a brown hen; with a grizzled hackle The wings are four in number, and should lie flat on the back. If dressed as a hackle, a brown grizzled feather from the back of a cock is the best; and the body may occasionally be varied by the use of the fur from the body of a brown spaniel, mixed with mohair of a dark red or claret cast, and ribbed with orange silk. It appears about the end of May, and continues for two months. It is a good fly at all hours of the day, if the water be not very low.

No. 23. The little Pellow May or Willow fly

resembles the green drake in form, and is composed of nearly the same materials, but on a much smaller scale. The body of yellow fur from the martin's neck; or yellow worsted unravelled, and mixed with a very small quantity of the fur from the hare's ear, so arranged that the yellow shall predominate as the colour of the belly; wings of the mallard's feather dyed yellow; or it may be made as a hackle fly, with a white cocking feather dyed of the same shade of yellow. This fly comes on early in May, and is the precursor of the green drake; until the appearance of which it may be used with success.

No. 24. a little brown fly which appears in June, and continues until September, is a good fly before sunset in a warm evening. The body of dark brown fur ribbed with orange silk; and a hackle of a greenish tinge from the back of a woodpecker, or dusky green parrot.

PLATE VII.

No. 25. is a brown winged fly, which is frequently seen during the months of June, July, and August. The body is of dark blue fur mixed with a portion of black sheep's wool; the wings from the brown feather of grouse; and a dark cock's hackle for legs. It is a good fly in still water, where it playfully skims the surface, somewhat in the manner of the Harry Long Legs.

No. 26. The Brown Dun.

The form of this fly resembles the blue dun, but it is rather less in size. The body is made of otter's fur mixed with lemon-colour mohair; a ginger hackle for legs; and the wings from a fieldfare. This, as well as all the dun flies of the same form, is a great favourite of the Trout; and is taken principally in the evening towards the approach of dusk.

No. 27. The Green Drake or May fly

is one of the most beautiful of our English insects, and is taken with avidity by the Trout and Chub, being a bait that they are remarkably fond of. These flies are to be found in the greatest plenty on sandy gravelly rivulets or brooks, and also on some large rivers; but their favourite haunts are

most commonly the smaller streams, where they are to be used with the best success. They appear about the twentieth of May, and continue for nearly a month. wings stand erect upon the back, and vary in the tints of yellow in different flies. The body is long, slender, and taper towards the tail, from the end of which spring the forked whisks, which turning up towards the back, give the name of Green Drake to this fly. The body is made of hog's down, or light bear's hair, intermixed with yellow mohair; or of barber's yellow silk only, warped with pale flos silk, and a small strip of peacock's harl for the head; a bittern's hackle is acknowledged to be the best imitation of the legs and dark stripes of the body; and for the tail the long hairs of sable or fitchet are most appropriate.

As no natural feather approaches the resemblance of the wings of this fly, it is necessary to have recourse to art for the imitation, which may be successfully produced by dying the spotted feathers of a wild mallard yellow, for which purpose a variety of recipes have been given. This fly kills extremely well at all hours of the day, particularly in still water.

Recipe for staining the Mallard's feather yellow, from "Walton and Cotton's Complete Angler," Edit. 1808.

Take the root of a Barberry tree and shave it, and put to it woody viss, with as much alum as walnut, and boil your feathers in it with rain water, and they will be of a very fine yellow.

Recipe for staining the same colour, from "Salter's Modern Angler," page 61.

Scrape a small quantity of the bark of the Barberry tree, or bruise in a mortar the root; add to it a lump of alum, and one or two dozen gray feathers of a mallard; boil them

in a pint of rain water in an earthen pitcher about an hour, and you will find them the colour you wish.

Another from the same Treatise.

When the Barberry cannot be readily procured, take of Turmeric one ounce, Alum half ditto, Stone Blue quarter ditto, each pounded fine; boil them with the gray feathers above described, and it will produce the same colour. It may prevent a mistake if you frequently take out a feather and dip it in clean water; you will then observe the progress of the dye.

Another from "Taylor's Angling in all its branches."

The best dye for all yellow materials for artificial flies is the bark from the branches of a Crab tree, taken in the Spring when the sap is up. Before you use it put any quantity that you want into a vessel, just cover it

with a mixture of one half hard water and the other half urine, and let it stand twentyfour hours; then put it into a proper yessel, with some alum according to judgment, so that it simmer over a slow fire about two hours; stir up all well together, and take out the bark; then put in your feathers and other materials, and stir them round till the liquor just begins to boil; then take them out, and instantly throw them into some hard cold water with a little alum dissolved in it, wash them out and dry them for use: you may make the shades of this colour vary by dissolving more or less of the bark according to judgment, or letting the materials be in the dye a longer or shorter time.

Another. 1 100

A subsect to be breaking to be a construction

Gumboge dissolved in spirits of wine will impart a fine yellow to the feathers, if they be first boiled in strong alum water.

s trançaj od alija a lili 🏝 s i salam ani pri

No. 28. The Blue Blow

is one of the smallest flies worthy the Angler's notice; nevertheless it must claim his particular attention, as when the water is low it is an excellent killer, and when these insects appear in large quantities the Trout are extremely active in devouring them. It is hardly possible to dress this fly upon too small a hook: the body should be made of any very dark blue fur, or of a peewit's topping, as its appearance on the water exactly resembles a lump of soot; the wings may be made of thistle down, or a bluish white hackle. It is a Summer fly, but is most abundant during the first fortnight in August, when at about one o'clock in the day the water is covered with them.

Ro. 29. The Black Midge

is another very minute fly, and is dressed with brownish black silk for the body, and a blue cock's hackle over it. It is chiefly to be used as a dropper when the water is fine, and is taken freely after a shower of rain in the evening during the Summer months.

Ao. 30. The Gray Drake

Last the attention

a had aka:

generally succeeds the green drake, although they are sometimes to be seen together in equal quantities. Its duration is about a fort-night; and it is to be found on almost all waters, whether large or small, rapid or otherwise. It is an excellent fly for attracting large fish, and may be used from three o'clock in the afternoon until dusk. In form and size it resembles the Max Fry; but in colour it is very different. The body is to be made of dirty white ostrich harl, or cream coloured crewel, dressed with flesh coloured silk, and ribbed with a dark grizzled cock's hackle; the head to be formed of peacock's harl, in the same manner as the


green drake; the wings of the mottled feather of the mallard, or mallard teal, provided it be not very dark; and the tail of the hair of sable, or fitchet's tail. This fly should be thrown directly over the fish, and so managed, if possible, that the wings may not touch the water.

No. 31. The Peacock fly

comes on early in the season, and is an excellent fly on gloomy days throughout the year. The body is made of dark peacock harl, and wings of starling, made to lie flat on the back; a grizzled hackle for legs, to be dressed with silk of mulberry colour.

No. 32. The Cinnamon Fly

has four wings, which are large in proportion to the body. They should be dressed full, and made from the pale reddish brown



Digitized by Google

feathers of a hen, which approach the colour of cinnamon; the body of any dark brown fur, and a ginger hackle for legs.

The writer has had excellent diversion with this fly in the months of August and September, in the Welch rivers; but has been unable to meet with any description of it in the several treatises upon Angling which he has from time to time perused. A representation is given in Walton and Cotton's Complete Angler, p. 342, plate 13, of a fly which in form exactly resembles this, but is of much larger dimensions; neither do the materials for composing it correspond with the description here given as to colour, &c.

PLATE VIII.

Nos. 33 and 34 represent the SAND FLY; the former with the wings raised, in order to shew the size of the body; the latter to point artificially.

ara Chaillean al al as mile

This may be considered as one of the best flies for affording diversion which can possibly be selected, for it may be used successfully at all hours of the day if from April to the end of September; and is equally alluring to Trout and Grayling.

he has from thee totions you all. It may be

Whilst on the borders of Yorkshire, where, as well as in Cumberland and Westmoreland, the snipe's wing and golden plover's feathers dressed as hackles without dubbed bodies are the favourite flies, the writer was induced by the recommendation of an experienced Angler to try them. During the morning, the weight and number of fish taken were nearly equal, say from three to four pounds each. Not satisfied with this diversion, as the fish were eagerly rising at something, the idea of trying the Santi fly suggested itself; the con-

sequence of which experiment was in a very short time a pannier well filled with fine Tront, amounting in weight to nearly sixteen pounds; whilst the other party, well acquainted with the river, had not caught half the weight. His astonishment at this success was extreme, as he said he was ignorant of the existence of such a fly: indeed so prejudiced are the generality of the fishermen of these countries in favour of the flies made from the snipe and plover, (which they regard as incomparable) that almost every other description is neglected by them,

The wings are made from the sandy coloured feather of the landrail's wing, with a ginger hackle for legs; and the bright sandy coloured fur from the hare's neck mixed with a very small quantity of orange coloured mohair for the body; or if dressed as a hackle, the feathers from under the throstle's wing are nearest the colour of the wings of the fly.

Mo. 35. The Great Red Spinner

is to be used with effect all the year, particularly when the water is clearing after a flood, and is of a dark brown or red colour. It has four wings; the two uppermost are of a red colour, those under are transparent and of a blue shade. It may be made with a starling's feather, and red hackle for the wings; and seal's fur or hog's down dyed red, and mixed with brown mohair, for the body. Or it may be dressed in the same manner as the MAR-LOW BUZZ, which is a fly of a similar description, but rounder in form and thicker in the body, somewhat resembling No. 4, in plate 4. For this fly the copper coloured feather of the peacock's tail is used for the body; and the inestimable cockis hackle, which is of perfect red, having a black stripe down the middle, wound pretty full over the body. This, and the SAND FLY before described, may be considered STANDARD flies.

Mo. 36. The Pale Ebening Dun

approximates to a yellow, and is taken extremely well late in the evening of a calm Summer's day. The body is made of martin's yellow fur, with a little mouse's fur mixed with it; the wings of the mallard's feather dyed of a very pale yellow, or with a pale ginger cock's hackle. The same process will answer for staining this colour as is recommended for the green drake; but it must not be allowed to imbibe too deep a tinge.

s.b. mod agrify all.; mbb delaward a ling **Ao. 37. The Blue Gast** gas di**no :** had aword dispulled a herostas.

is a small delicate fly, and an excellent bait for Grayling in the months of September and October. The wings must be made very small, from the snipe's wing; or, as is equally to be recommended in all small flies, of a hackle of a bluish dun colour: the body of dark moleskin, wrapped with bright purple silk.

Ao. 38. The Oak fly, Downlooker, or Canon fly,

is to be found in April, May and June, on ash trees, oaks, willows, or thorns, growing near the water. Its head is always pointed downwards, whence it obtains the name of downlooker. The wings are short in proportion to the body, and lie flat on the back. The colours of this fly being various and unequally mixed, make the imitation dif-The head of the fur from the hare's ear; body under the wings dun fur, in the middle orange and yellow, and towards the tail a brownish dun; the wings from the feather of a yellowish brown hen; or it may be made with a bittern's hackle only, without wings. It is an excellent fly both for dibbing in the natural state, and using artificially.

No. 39. The Great Black Ant

commonly appears in warm gloomy weather, from the middle of June to the latter end of

August. The ANT FLIES are excellent killers from eleven piclock in the forenoon until six in the evening, and they may be used in still water as well as streams. The wings of this fly are made of the lightest blue feather from under the snipe's wing, or from the tom-tit's tail. Some make them of this tle's down; but its want of durability is a great objection to the use of this material, unless for a fly that remains on the water for a very short time, which is not the case with the ant flies. The body of black ostrich harl made thick at the tail and under the butt of the wings, with a reddish brown hackle for legs.

The Tro. 40. The Creat Red Ant all and a land

resembles the preceding in size and form, appears about the same time, and is to be used during the same hours of the day. The wings are to be made of a light starling's

delicates this ings, which are four, lie flat

feather; body in the same manner as described for the black ant, of gold coloured mohair, or copper coloured peacock's harl, with a ginger backle for legs.

sold to the To. Who sixtars in San Ar.

No. 41. represents the small black ant: both this and its companion of the same size are to be made of the same materials as directed for the large ants, but (as exhibited) on a much smaller scale.

No. 42. The Mellow Sally Fly

is to be used early in May, being one of the flies which prepare the fish for the green and gray drakes. In appearance it is extremely delicate: the wings, which are four, lie flat on the back, and are to be made of a dyed feather or hackle; the body of yellow martin's fur, crewel or mohair.

The description of the flies represented in the plates being here concluded, it remains

only to direct the attention of the reader to such of them as may be considered standard flies, and of which he ought first to make trial when he visits a river with which he is not familiar. He should have two lines with three flies affixed to each; for the first attempt he may use the March brown, (or later in the season a reduced fly of the same form and materials) at the point, with a dun hackle, having the body light or dark to suit the day, for the first dropper; the second dropper a red hackle with peacock body. If these flies do not raise fish, after trying two or three streams, it will be advisable to change them, and put on the following, viz: at the point the Sand fly, first dropper, grouse hackle or wren's tail with orange body; second dropper, a pale yellow or cream-coloured hackle over a bluish body, or one of the ant flies, as a variety from the preceding five. The bodies of the hackles are to be dressed large or small in proportion to

the water. With some of these flies an experienced Angler will take abundance of fish all the year round; and it will be time enough for him to change them, when he shall correctly have ascertained which fly is the favourite of the fish for the time being.

No fisherman should commence his operations in the morning without having a reserve of at least triplicates of his flies; for he will find it extremely mortifying, should accident deprive him of a particular fly at which the Trout were rising freely, not to have another of corresponding colours and form to substitute in its place.

OF THE MOTHS,

FOR

night fishing.

Although the Angling by night has a close affinity to Poaching; and as such is beneath

the notice of a gentleman, yet as in extreme droughts during the Summer months it may be difficult to procure a dish of fine fish, however urgent the necessity, and as this method is decidedly more sportsman like than the use of the net, a description of the two baits most likely to succeed is subjoined for the benefit of such persons as may chuse, for the sake of a dish of fish, to expose themselves to the heavy dew of a Summer's night.

The wings of the WHITE MOTH are made from the feather of a white owl; the body of white ostrich harl, and a white cock's hackle over it. If a gentle be added, the success will be more certain.

The wings of the BROWN MOTH are to be made from the wings of the brown owl, or the back feathers of a brown hen; the body of dark bear's hair, and a brown cock's hackle over it. A cod-bait, as being hearer

the colour of the body, is preferable to a gentle for this fly.

Both these moths are to be dressed rather larger than the green or gray drakes, and may be used until the approach of dawn. The fish will be heard to rise at them very distinctly, at which moment the Angler must strike.

Method of preserving Gentles.

These baits having been mentioned several times in the foregoing pages, it may be expected that some instructions should be given as to the method of procuring and preserving them.

Take the liver of any animal, and hang it over a barrel half full of dry clay, and as the gentles grow large they will fall into the barrel and scour themselves, and will be always ready for use; or, if it be required to keep them all the year, procure some dead animal which is fly blown, and when the gentles begin to be alive and stir, bury the carcase and them together in soft moist earth free from frost; these gentles may be dug out as they are wanted, and will be fit for use until March, at which time they will turn to flies.

GROUND FISHING FOR TROUT

. हें हैं के कार केंद्र हैं है है कि सम्बर्ध के

na kang ng palikitan sa sa babin

while soil in the pall to a most ag

Caption and WITH A RUNNING LINE 2001 of

When the rivers are thick and discoloured so as to prevent the use of the fly, good -Trout are to be taken with a running line without float, so leaded that it shall just touch the ground without resisting the force of the stream: the lead should be fixed

about eight inches from the hook, and may consist of two or more shot, in size according to the strength of the current. The best baits are well scoured lob or dew worms, or a couple of brandlings; and the edges of streams are the most likely for sport. The line should be so held as to admit the perception of the slightest impediment; for when it stops the Angler should strike, as he will generally find the cause of the hindrance to have proceeded from the biting of a fish.

This diversion is so inferior to that which fly fishing affords, that few who have the opportunity of making choice will hesitate in their preference of the latter; but when fishermen make distant excursions from home for the express purpose of indulging their inclination for the amusement of Angling, they ought to be enabled to avail themselves of every fair method which may yield them sport.

OF

TROLLING.

OR

MINNOW FISHING.

Next to the use of the artificial fly this is the most sportsman-like and successful method of killing Trout. Those minnows are to be chosen which are of middle size, and brightest under the belly: where they are to be found in shoals, as in the case in most Trout streams, the landing net, if made of large dimensions, as recommended under the list of necessaries, will with very little trouble supply an ample stock of bait.

The best way of baiting the minnow is to draw the large hook first through both lips, so that they be not torn, and then insert it at the mouth and pass it down the body, until the point protrudes below the ventral fin; the two small hooks must then be fastened through the back of the head, so that they may stand upright with the points towards the head. Some use three small hooks for this purpose; but as the fish take this bait greedily, two in addition to the body, or large hook, are sufficient. The chief consideration is the spinning of the minnow, which cannot turn too quickly; a couple of double box swivels will greatly facilitate this object.

The great advantage of minnow fishing is, that it may be most successfully practised at those periods when the water is unfit for the use of the fly, as the strongest streams are best for this purpose, when the water is clearing after a flood, or is thickened or discoloured from any other cause.

The line must be thrown across the stream, and the bait kept in continual motion by

spinning it towards the Angler. The action in striking must be perpendicular, or there will be a risque of the bait being drawn from the mouth of the fish; the rod must be then kept upright, and the fish played in the same manner as before described. Nobb's treatise on this subject, lately reprinted and attached to Best's Art of Angling, will furnish the minnow fisher with every information which may be requisite.

Having thus treated of all the modes of Angling in rivers which afford exercise as well as amusement, the compiler leaves to other hands the task of shewing the use of night lines, salmon roe, spears, and nets, all of which are beneath the notice of the fair Angler and true sportsman. He cannot but regret the incalculable injury which rivers sustain from these implements: this can only be prevented by gentlemen possessed of manorial rights giving encouragement to the

fuir Angler, who will have frequent opportunities, and will gladly do his utmost, publicly to expose such persons as may unlawfully trespass upon their rights. The use of a coracle in Angling by strangers ought always to excite suspicion; for it rarely happens that it is not made the vehicle of nets, night lines, or spears, which the occupier has the most favourable opportunities of using to advantage.



PRINTED BY G. F. HARRIS'S WIDOW AND BROTHERS, LIVERPOOL.

Digitized by Google

PRESERVATION SERVICE

SHELFMARK 1040. 4.35

THIS BOOK HAS BEEN MICROFILMED (20 0 S) N.S.T.C.

MICROFILM NO SEE RPM

